

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

NOVEMBER 1961



VOL. LVI. NO. 11

FIFTY-SIXTH YEAR OF PUBLICATION

PRICE 3s.

ANNUAL SUBSCRIPTION 34s. POST FREE. \$3.00 in Canada and U.S.A.

LEADING CONTENTS

	PAGE
Concrete and Europe	367
Book Reviews	370
Forces in Three-dimensional Groups of Piles.—I	
By W. E. Scriven, B.Sc.(Eng.)	371
A Bridge in Northern Ireland	
By John Faber, B.Sc., M.I.C.E.	379
The Works of the Late Professor Eduardo Torroja	385
The New Grandstand at Ascot	389
The Design of Doubly-reinforced Flanged Beams by the Load-factor Method	
By Yüksel Sezginer, Dipl. Ing. (Turkey)	397
Box-frame Construction in Sweden	404

No. 648

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE

For Catalogue of "Concrete Series" books on
concrete and allied subjects, send a postcard to:

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1.

INDEX OF ADVERTISERS

	Page		Page
A.B. MOULD & CONSTRUCTION CO. LTD.	xvii	LAPARDE ALUMINOUS CEMENT CO. LTD.	xviii
A.C.E. MACHINERY LTD.	liv	LAWLER AYERS & CO. LTD.	xviii
AMELSON & CO. (ENGINEERS) LTD.	xxvii	LAW & SON (STAINERS) LTD.	—
ALLAN, P. F. & CO. LTD.	lxv	LECA (GREAT BRITAIN) LTD.	—
ALLIED BUILDING COMMODITIES	—	LEICA OPT. & GREASE CO. LTD.	xviii
ANGLIAN BUILDING PRODUCTS LTD.	—	LEICESTER LTD.	xlv
ATLAS STONE CO. LTD.	—	LEVERTON (INDUSTRIAL) LTD.	xliii
AVON MANUFACTURING (WARWICK) LTD.	—	LELLINGTON, GEORGE, & CO. LTD.	lvii
BARTOLINE (HULL) LTD.	—	LIND, PETER, & CO. LTD.	v
BARVET, A. & C. LTD.	—	LOGAN, DUNCAN (CONTRACTORS) LTD.	—
BERRY'S ENGINEERING CO.	xxii	LONGER, GEORGE, & SON LTD.	—
BOULDER EQUIPMENT LTD.	—	McCALL & CO. (SHEFFIELD) LTD.	viii
BOYER, WM., & SONS LTD.	lxii	McCALLS MACALLOY LTD.	xliii
BRAITHWAITE & CO., ENGINEERS LTD.	xxix	McKINNEY FOUNDATIONS LTD.	xxix
B.R.C. ENGINEERING CO. LTD.	lxviii	McLAUGHLIN & HANVEY LTD.	vii
BRETT, ROBERT, & SONS LTD.	—	MACHINERY (CONTINENTAL) LTD.	—
BRITISH OXYGEN CO. LTD.	—	MASCHETTE LTD.	—
BRITISH STEEL PILING CO. LTD.	—	MASSEY, A. H., LTD.	xliii
BUILDING & CONSTRUCTION CO. LTD.	—	MAY & BUTCHER LTD.	xlii
BYRD, A. A., & CO. LTD.	lviii	MILBANK FLOORS LTD.	lxiii
CABLE COVERS LTD.	lxix	MILLARS' MACHINERY CO. LTD.	lxviii
CALEDONIAN MECHANICAL HANDLING CO. LTD.	xxiii	MILLS SCAYFOLD CO. LTD.	—
CAPLIN ENGINEERING CO. LTD.	xliv	MODULAR CONCRETE CO. LTD.	lxviii
CASTLEHILL SAND & GRAVEL CO. LTD.	—	MONK, A., & CO. LTD.	xxvii
CEMENT MARKETING CO. LTD.	xix	MULCASTER, WM., & CO. (CONTRACTORS) LTD.	xxvii
CEMENT & STEEL LTD.	iv	MYERS, FRID., LTD.	xxiii
CHERTMAN, ALEX. J., LTD.	xi	OMERIA CONSTRUCTIONS LTD.	—
CHEMICAL BUILDING PRODUCTS LTD.	xli	OVERSEAS COMMODITIES (SOC) LTD.	xxvii
CHRISTIAN & NISLAKE LTD.	—	P.S.C. EQUIPMENT LTD.	xxvii, xxviii
CORRIE, GEORGE, SONS & CO. LTD.	—	P.Z. PRESTRESSING CO. LTD.	xxviii
COLCRETE LTD.	xli	PASHLEY & TRICKETT LTD.	—
CONCRETE PILING LTD.	—	PIERHEAD LTD.	—
CONCRETE PROOFING CO. LTD.	lxix	PITMAN, SIR ISAAC, & SONS LTD.	—
CONCRETE PUMP CO. LTD.	xvi	PORTLAND LTD.	lxvi
CONVEYORS & CO. LTD.	xi	POWELL DUFFY'S TIMBER INDUSTRIES LTD.	—
CONVEYOR EQUIPMENT CO. LTD.	—	PRESTRESSING SALES LTD.	lxv
COSTAIN CONCRETE CO. LTD.	—	PRIST, B., & SONS LTD.	xxviii
COWLIN, WM., & SON LTD.	—	PUMPCART HIRE CO. LTD.	lix
CROYDON REINFORCED PIPEWORKS CO.	—	RANALAN STEEL MOULDS LTD.	xi
D.A. MODELS LTD.	lxix	ROYAL CAR CO. LTD.	xxviii
DANDRIDGE, J. & A., LTD.	—	RUMB & TONYN—PAULING GROUP	—
DAVIDSON'S FAYER SALES LTD.	lxvi	RYLANDS BROTHERS LTD.	xxv
DE JONG	—	SEALOCRETE PRODUCTS LTD.	iv
DICKENS, STUART B., LTD.	ix	SHARP JONES & CO. LTD.	—
DORMAN LONG & CO. LTD.	—	SIMPLEX CONCRETE PILES LTD.	xxix
DOUGLAS, ROBERT M. (CONTRACTORS) LTD.	—	SOMERSET WIRE CO. LTD.	lxix
DURATURE & WIRE LTD.	i	SPENCER WIRE CO. LTD.	lxix
ENGINEERING DESIGN & CONSTRUCTION LTD.	lviii	STELMO LTD.	lxix
ERSTON BROS.	—	STEIN PRECAST CONCRETE LTD.	lxviii
EXPANSTE LTD.	xliv	STIC B PAINT SALES LTD.	li
FARR, A. E., LTD.	—	STONE COURT BALLAST CO. LTD.	lxviii
FLEXIBLE DRIVE & TOOL CO. LTD.	lvi	STORER, WM. T., & CO. LTD.	xxviii
FONDEDULE, SOC. AN., INC.	xxvii	STRESSING DEVELOPMENTS LTD.	—
FORD MOTOR CO. LTD.	lxiii	STUART'S GRAPHOLITHIC CO. LTD.	lvi
FRANKFELD LTD.	vi	SUMNER & DORNING BRICK COS. LTD.	—
G.K.N. REINFORCEMENTS LTD.	lxix	TARMAC LTD.	—
GLEASON, M. J. (CONTRACTORS) LTD.	lxix	TECHNICAL PAINT SERVICES	—
GOODES ENGINEERING LTD.	—	TENTOR BAR CO. LTD.	—
GURITE CONSTRUCTION CO. LTD.	lxviii	THAMES PLUMBING MANUFACTURERS LTD.	ix
HALL & CO. LTD.	—	THOMAS & CO. LTD.	—
HEAD WRIGHTSON TERESDALE LTD.	xliv	T.F. POLYPLASTIC CONCRETES LTD.	—
HILTON GRAVEL LTD.	—	TRENT GRAVELS LTD.	lxix
HOLMERS PILES LTD.	—	TRITON ENGINEERING CO. (SALES) LTD.	xv
HOLLY & CO. LTD.	—	TRUCK-MIX (MIDLANDS) LTD.	—
HUNTLEY & SPARRE LTD.	—	TUNNEL PORTLAND CEMENT CO. LTD.	lxviii
IBRAL CEMENTS (READING) LTD.	—	UNITRUST DIVISION OF SAKREY-SHELDON LTD.	—
IMPERIAL CHEMICAL INDUSTRIES LTD.	—	VOLKMAN, O. A.	lxii
JOHNSON, RICHARD, & NEPHEW LTD.	lxvii	WALKER WRIGHT & CO. LTD.	lxviii
JONES, T. C., & CO. LTD.	—	WELBEC (STEEL STOCKHOLDERS) LTD.	—
KANGO ELECTRIC HAMMERS LTD.	—	WELLSMAN BROS. LTD.	—
KENRAL LTD.	xxx	WESTWOOD, JOSEPH, & CO. LTD.	lxii
KENDALL'S STONE & PAVING CO. LTD.	—	WHITCROSS WIRE CO. LTD.	—
KERRIE-GREENWOOD & CO. LTD.	lxiv	WHITHEAD IRON & STEEL CO. LTD.	x, xi
KIRK, J. L., & CO. LTD.	—	WHITLEY MORAN & CO. LTD.	lii
KING, J. A., & CO. LTD.	lii	WILSON, ROY, DICKSON LTD.	lii
		WINGET LTD.	lxix
		WOLF ELECTRIC TOOLS LTD.	lxix
		YORKSHIRE HENRIQUE CONTRACTING CO. LTD.	lxvii

LYE

SULPHITE

IN LIQUID FORM

**an important additive for
concrete · grout · and most
forms of ground treatment**

Liquid Sulphite Lye is an effective cement expander, whereby cement shrinkage is obviated, leaving the concrete free from shrinkage cracks. For mass concrete it avoids the deleterious effects of thermal contraction and shrinkage. It is also invaluable for grouting work, and for prestressing cable ducts it ensures that when the grout is set it always completely fills the cable duct and other apertures. Its qualities for ground treatment and tunnelling work have also been proved on important contracts.

Liquid Sulphite Lye is the most effective and economical material for producing air-entrained and colloidal concrete, and will satisfy the most exacting requirements for this class of work.

Sulphite Lye is available at short notice in drums or road tank wagons. Send for samples and prices.

ROY WILSON, DICKSON LTD

1 NORTH JOHN ST, LIVERPOOL 2

Tel: Central 7691

INDEX OF ADVERTISERS

	Page		Page
A.B. MOYLE & CONSTRUCTION CO. LTD.	xvii	LARGE ALUMINOUS CEMENT CO. LTD.	xviii
A.C.E. MACHINERY LTD.	iv	LAWLER AVENUE & CO. LTD.	xviii
ARLSON & CO. (ENGINEERS) LTD.	xvii	LEA & SON (SHARPS) LTD.	—
ALLAN, E. F., & CO. LTD.	xv	LEA (GREAT BRITAIN) LTD.	—
ALLIED BUILDING COMMODITIES	—	LEEDS OIL & GREASE CO. LTD.	xviii
ANGLIAN BUILDING PRODUCTS LTD.	—	LAPCHUTE LTD.	xiv
ATLAS STONE CO. LTD.	—	LEVYTON (INDUSTRIES) LTD.	xviii
AVON MANUFACTURING (WARWICK) LTD.	—	LILLINGTON, GORDON, & CO. LTD.	xv
BARTOLINI (HILL) LTD.	—	LIND, FRYER, & CO. LTD.	—
BARTY, A. & CO. LTD.	—	LONGAN, DUNCAN (CONTRACTORS) LTD.	—
BERRY'S ENGINEERING CO.	xvii	LONGER, GEORGE, & SON LTD.	—
BOULDER EQUIPMENT LTD.	—	MACALL & CO. (SHREFFIELD) LTD.	xvii
BOYCE, Wm., & SON LTD.	xvii	MACALLS MACALLOV LTD.	xvii
BRAITHWAITE & CO., ENGINEERS LTD.	xviii	McKINNEY FOUNDATIONS LTD.	xvii
B.R.C. ENGINEERING CO. LTD.	xviii	McLAVOCHIE & HARVEY LTD.	—
BRETT, ROBERT, & SONS LTD.	—	MACHINERY (CONCRETE) LTD.	—
BRITISH OYSTER CO. LTD.	—	MAONITE LTD.	—
BRITISH STEEL PILING CO. LTD.	—	MAGNET, A. H., LTD.	xviii
BUILDING & CONSTRUCTION CO. LTD.	—	MAY & BUTCHER LTD.	xvii
BVED, A. A., & CO. LTD.	xvii	MILBANK FLOORS LTD.	xviii
CABLE COVERS LTD.	xvii	MILLAR'S MACHINERY CO. LTD.	xviii
CALDERMAN MECHANICAL HANDLING CO. LTD.	xviii	MILLS SHAPFORD CO. LTD.	—
CAPLIN ENGINEERING CO. LTD.	xvii	MORGAN CONCRETE CO. LTD.	xviii
CARTERELL SAND & GRAVEL CO. LTD.	—	MOORE, A., & CO. LTD.	xviii
CEREST MARKETING CO. LTD.	iv	MULCAHY, Wm., & CO. (CONTRACTORS) LTD.	xviii
CEMENT & STEEL LTD.	—	MURPHY, FRAS. LTD.	xviii
CHRISTIAN, ALEX. J., LTD.	xv	CHERIN CONSTRUCTIONS LTD.	—
CHEMICAL BUILDING PRODUCTS LTD.	xv	OVERMAN CONCRETE (SOL.) LTD.	xviii
CHRISTIAN & NIELSEN LTD.	—	P.S.C. EQUIPMENT LTD.	xviii
CHES, GEORGE, SONS & CO. LTD.	—	P.E. PRESTRESSING CO. LTD.	xviii
COLNETE LTD.	xv	PURLEY & TRENCH LTD.	—
CONCRETE PILING LTD.	—	PURNEAD LTD.	—
CONCRETE PAVING CO. LTD.	xvii	PYTHAN, SH. ISAAC, & SONS LTD.	—
CONCRETE PUMP CO. LTD.	xvi	PORTLAND LTD.	xvii
CONVEYANCE & CO. LTD.	xv	POWELL DUNNIN TOWER INDUSTRIES LTD.	—
CONNELLY EQUIPMENT CO. LTD.	—	PRESTRESSING SALES LTD.	—
CONTAIN CONCRETE CO. LTD.	—	PRINCE, B., & SONS LTD.	xviii
COWLEN, Wm., & SON LTD.	—	PURKINS HIRE CO. LTD.	xv
CROYDON REINFORCED FIBREGLASS CO.	—	RANALAS STEEL MOLDING LTD.	xv
D.A. MODELS LTD.	xvii	ROVER CAR CO. LTD.	xviii
DARBRIDGE, J. & A., LTD.	—	RUM & TOMPSON—PAULING GROUP	—
DARTMOUTH FARM SALES LTD.	xvii	RYLANDS BROTHERS LTD.	xv
DE JONG	—	SLACKS PRODUCTS LTD.	xv
DICKINSON, SCUART B., LTD.	xv	SHARP JONES & CO. LTD.	—
DORMAN LONG & CO. LTD.	—	SHARPLE CONCRETE PILES LTD.	xvii
DOUGLAS, ROBERT M. (CONTRACTORS) LTD.	—	SHERREY WIRE CO. LTD.	xvii
DUNAVIS & WIRE LTD.	1	SPEAKER WIRE CO. LTD.	xvii
ENGINEERING DESIGN & CONSTRUCTION LTD.	xvii	STEELCO LTD.	xvii
EXP-OF BROS.	—	STEVY PRECAST CONCRETE LTD.	xvii
EXPANITE LTD.	xv	STON B FINEST SALES LTD.	xv
FARR, A. E., LTD.	—	STONE COURT BALLARY CO. LTD.	xvii
FLEXIBLE DRIVE & TOOL CO. LTD.	xvii	STRONG, Wm. T., & CO. LTD.	xvii
FONDEDIA, SOC. AN., INC.	xvii	STRONGHOLD DEVELOPMENTS LTD.	—
FORD MOTOR CO. LTD.	xvii	STUART'S CARBONIZING CO. LTD.	xvii
FRANKFELD LTD.	xv	SUNNER & DUNNING POWER CO. LTD.	—
G.M.N. REINFORCEMENTS LTD.	xvii	TAKING LTD.	—
GLEDSON, M. J. (CONTRACTORS) LTD.	xvii	TECHNICAL PAINT SERVICES	—
GOODS ENGINEERING LTD.	—	TENTON BAR CO. LTD.	—
GUNITE CONSTRUCTION CO. LTD.	xvii	THAMES PLYWOOD MANUFACTURERS LTD.	xv
HALL & CO. LTD.	—	THOMAS & CO. LTD.	—
HEAD WOODHEAD TREDAIR LTD.	xv	T.P. POLYPLASTIC CONCRETE LTD.	—
HILTON GRAVEL LTD.	—	TRENT GRAVEL LTD.	xvii
HOLMES & PIERCE LTD.	—	TRETON ENGINEERING CO. (SALES) LTD.	xv
HOLST & CO. LTD.	—	TRUCK-MIX (MIDLANDS) LTD.	—
HUNTLEY & SPAIN LTD.	—	TUNNEL PORTLAND CEMENT CO. LTD.	xvii
INDAL CEMENTS (READING) LTD.	—	UNITED DIVISION OF SAREY-SHELDON LTD.	—
INDUSTRIAL CHEMICAL INDUSTRIES LTD.	—	VOLEMAN, O. A.	xvii
JOHNSON, RICHARD, & NEPHEW LTD.	xvii	WALKER WRIGHT & CO. LTD.	xvii
JONES, T. C., & CO. LTD.	—	WELBROCK (STEEL STOCKHOLDERS) LTD.	—
KAPRO ELECTRIC HARMERS LTD.	—	WELLSHIRE PROD. LTD.	—
KEMAL LTD.	xvii	WELSHMAN, JONES, & CO. LTD.	xvii
KENDALL'S STONE & PAVING CO. LTD.	—	WHITCHURCH WIRE CO. LTD.	xv
KERRER-GREENWOOD & CO. LTD.	xvii	WHITFIELD LIGN & STEEL CO. LTD.	xv
KIER, J. L., & CO. LTD.	—	WHITLEY MOHAY & CO. LTD.	xv
KING, J. A., & CO. LTD.	xv	WILSON, ROY, DICKSON LTD.	xv
		WINGET LTD.	xvii
		WOLF ELECTRIC TOWER LTD.	xv
		YORKSHIRE REINFORCEMENT CONTRACTING CO. LTD.	xvii

SULPHITE LYE

IN LIQUID FORM

**an important additive for
concrete · grout · and most
forms of ground treatment**

Liquid Sulphite Lye is an effective cement expander, whereby cement shrinkage is obviated, leaving the concrete free from shrinkage cracks. For mass concrete it avoids the deleterious effects of thermal contraction and shrinkage. It is also invaluable for grouting work, and for prestressing cable ducts it ensures that when the grout is set it always completely fills the cable duct and other apertures. Its qualities for ground treatment and tunnelling work have also been proved on important contracts.

Liquid Sulphite Lye is the most effective and economical material for producing air-entrained and colloidal concrete, and will satisfy the most exacting requirements for this class of work.


Sulphite Lye is available at short notice in drums or road tank wagons. Send for samples and prices.

ROY WILSON, DICKSON LTD

1 NORTH JOHN ST, LIVERPOOL 2

Tel: Central 7691

BAR-BENDING EQUIPMENT




RAS.40 MODEL

This is a single-disc machine which is specially designed for an extraordinarily high rate of bending bars up to $1\frac{1}{2}$ in. diameter.

A full hook takes three seconds' bending time. It is also equipped with accessories for bending angle loops in one operation on mild steel reinforcement up to 1 in. diameter.

HOOPS & SPIRALS

We supply, at extra cost, an appliance (illustrated here) for use with RAS.40 and ARD.50 models for the bending of hoops and spirals. Bends radii of 11 in. and upwards and to any pitch of spiral.



Our Bending Equipment also includes the ARD.50 model—a double-disc machine for bending bars up to 2 in. diameter. We also supply, at extra cost, formers and backrests for special steel such as "Square Grip," "Twiststeel," etc., which can be fitted to the ARD.50 and RAS.40 models. Full details are available on request. All machines are available for Sale or Hire.

CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT

Telephone: Chatham 45580.

Telegrams & Cables: Cambelgi, Chatham

DRILLED FOUNDATIONS



Architects
Consulting Engineers
Main Contractors

Sir John Berrill, Fairs and Partners
One Aired and Partners
Freelance and Civils Limited

A modern office block which is being erected
on our drilled foundations at Vauxhall Bridge
Rd London for Chesterfield Properties Limited

We have modern mobile plants which can
drill foundations of various diameters up to
depths of 100 feet or more. Tel: Abbey 7361
or send your enquiries to

PETER LIND

Peter Lind and Company Limited Romney House Tufton Street London SW1

here's **ONE SYSTEM** of Piling...



do you know about
THE OTHER SIX?

*Write or phone Abbey 6006,
for your copy of this brochure*



FRANKI PILE

FRANKI PILE LIMITED • 39 VICTORIA STREET • LONDON • S.W.1

A REINFORCED CONCRETE BRIDGE AT MAGHERAMORNE, Co ANTRIM

This reinforced concrete bridge was specially designed and constructed to carry large basalt dumpers to a tip in Larne Lough. Despite considerable difficulties encountered in siting the foundations, the superstructure was cast insitu, using a complete bird-cage scaffolding to facilitate the construction, which was completed in seven months.


Bridge at Magheramorne, Co Antrim for the British Portland Cement Manufacturers Ltd. Consulting Engineers: Messrs. Oscar Faber & Partners.

MCLAUGHLIN & HARVEY LTD

BUILDING AND CIVIL ENGINEERING CONTRACTORS

BELFAST

LONDON · DUBLIN · LONDONDERRY



FABRIC REINFORCEMENT by McCALLS

FABRIC • BARS • TENTOR • BENDING • MACALLOY • DESIGN

McCALL & CO (SHEFFIELD) LTD.

McCALLS MACALLOY LIMITED

TEMPLEBOROUGH • SHEFFIELD • ENGLAND • P.O. BOX 41

Telephone: ROTHERHAM 2218 (P.B. Ex 8 lines)

LONDON: SLOANE 0428

BIRMINGHAM: ACOCKS GREEN 0229

PORTSMOUTH: COSHAM 78702

MANCHESTER: BLACKFRIARS 1018


Which way to Boreham Wood?

Digging away at his private underground system the mole rarely reaches daylight—his is a case of forever working in the dark.

Much the same is true of concrete work when the newly-laid concrete becomes hidden from sight behind shuttering or moulds. It matures unseen until the time comes for the timber to be struck. What then?

If the timber is treated with MOLDCOTE, the outcome is certain: ultra-smooth surfaces, without blemish or stain.


MOLDCOTE is only one of the many SBD products used in the concrete industry. Whatever or wherever your concern is with top-class concrete, there is no wiser first step than to get in touch with us at Boreham Wood.



STUART·B·DICKENS LTD.

Manor Way, Boreham Wood, Herts · Telephone: Elstree 2211





.....
have been regularly used
.....
by leading Contractors for
.....
reinforced concrete work
.....
since 1903
.....

We were the pioneers in the supply of steel bars for reinforced concrete work and have given to the industry over 50 years of unbroken service, unequalled for quality and dependability. Contracts on which WHITEHEAD STEEL has been used include some of the largest and most important in the country.

We can supply mild steel with an ultimate tensile stress of 28/33 tons to the square inch, medium tensile 33/38 tons to the square inch, and high tensile 37/43 tons per square inch.

We can also supply high tensile bars 40/45 tons to the square inch with a minimum yield of 60,000 pounds per square inch.


THE WHITEHEAD IRON & STEEL CO. LTD.
NEWPORT TEL. NO. NEWPORT 4581 (1960) MON.

LONDON OFFICE: Steel House, Tothill Street, S.W.1. Telephone: Whitehall 2984/5.

BIRMINGHAM OFFICE: King Edward House, New Street, 2. Telephone: Midland 0412/3.

MANCHESTER OFFICE: Chronicle Buildings. Telephone: Blackfriars 1603/4.

GLASGOW OFFICE: 50 Wellington Street, C.2. Telephone: Central 1528.



OUTSTANDING BUILDING ...

Outstanding Products

**CHEMICAL
BUILDING
PRODUCTS LTD**
Warple Works
Cleveland Road
Hemel Hempstead
Herts

Telephone:
BOXMOOR 4900
(5 lines)
Telegrams: Prolithu
Hemel Hempstead

PROLAPIN Liquid Cement Waterproofer
LITHURIN Concrete Floor Hardener
QUICKSocrete P. Q. & D. Rapid Hardeners
and Setters
WETEXI 'S' Colourless Silicone Waterproofer
CONPLAST Concrete Plasticiser
CONPLAST 'W' Anti-freeze and Plasticiser
CONBEX Plasticised Expanding Grouting Material
CEBEX 112 Mortar Improver
CEBEX 113 Expanding Grouting Material
CEBEX 124 Multi-purpose Slurry Liquid
ROAD CONPLAST Air Entrainer and Plasticiser
LIFTOYL Floor Cleaner and Degreaser
ORKIT & TEKTAM Bituminous Coating and
Compounds
CONCURE Concrete Curing Agent
NITOLUX & ROBRITE Paints

NEW!! SCREEDEX the ideal Screed Additive.

CHEMICAL BUILDING PRODUCTS LTD

A ROAD GANG'S BEST FRIEND IS A FORD ENGINE

Road-building equipment powered by a Ford Industrial engine starts with two major advantages—the heart of it is a tough, hard-working, reliable power-unit built to the most modern designs, and behind it is the famous Ford Service Organisation—a world-wide chain of factory-trained engineers with stocks of genuine Ford parts.

Diggers, dumpers, cranes, compressors, road finishers, rollers, etc—all are available with Ford power-units, petrol or diesel.

Please send the coupon below for details of the Ford-powered equipment you are interested in.

FORD
SPELLS POWER

Please send me details of Ford-powered equipment of the following types


Type or class of equipment _____

NAME _____

ADDRESS _____




TO: FORD INDUSTRIAL ENGINE DIVISION • DEPT G5b/R6 • SOUTH OCKENDON • ROMFORD • ESSEX • ENGLAND



Modern roads demand that joint-fillers and top-sealers will withstand the most rigorous conditions of constant heavy high-speed traffic and exposure to weather.

Expandite Limited provide the unique expansion joint-filler, **FLEXCELL*** (specially manufactured by Celotex Ltd.)—a bitumen impregnated sugar cane fibre-board with remarkable recovery powers to solve the problem of sound joint-filling. Top-sealed with Expandite's **PLI-ASTIC**®, a hot-poured rubber/bitumen sealing compound. **FLEXCELL*** and **PLI-ASTIC*** are specified by Civil Engineers and Public Authorities the world over.

* Regd. Trade Marks



**ANOTHER
JOINTING
PROBLEM
SOLVED**

**EXPANDITE
LIMITED**

Specialists in the manufacture and use of Joint-Fillers, Sealing and Waterproofing Compounds, Concrete Additives, Anti-Corrosion Treatments and Mechanical Appliances

CHASE ROAD, LONDON, N.W.10.

Tel: ELGar 4321 (10 lines) and ELGar 1551 (10 lines)

36 Great North Road, Newcastle-upon-Tyne 2. Tel: Newcastle 23992
Trafford Park Road, Manchester 17. Tel: Trafford Park 1285/6

EXPANDITE (IRELAND) LIMITED

Greenhills Road, Walkinstown, Dublin. Tel: 501512

ASSOCIATES AND DISTRIBUTORS THROUGHOUT THE WORLD

TRITON VIBRATING SYSTEMS

REGD. TRADE MARK




vibrating precast concrete on the site
with mobile or fixed equipment . . .



Triton vibrating systems provide the Contractor with a completely planned vibrating unit for the production of precast concrete on the site. Our technical advice service will be pleased to suggest a comprehensive plan, using both mobile "Vibra-Lifta" tables and fixed tables (illustrated below) which will show the economy and efficiency to be obtained from using a Triton Vibrating System on the site.




The top illustration shows two Triton mobile "Vibra-Lifta" tables vibrating a 25-ft. precast beam. These "Vibra-Lifta" tables can be moved at will to any part of the site. The second illustration shows two Triton fixed tables vibrating a 15-ft. precast purlin. These tables can be mounted on concrete blocks of any required height. Complete technical details of these are available on request.



KINGSNORTH INDUSTRIAL ESTATE, WOTTON ROAD, ASHFORD, KENT

Telephone: Ashford 2051-2-3 Telegrams: Triton Ashford Kent



An Electrically Driven PC3 Concrete Pump with remixer. Capacities from 20 to 24 cu. yds. per hour. Ranges actually obtained 135 ft. vertical or 1,500 ft. horizontal. Also smaller model PC4—8-10 cu. yds. per hour.

EFFICIENT RECONDITIONING SERVICE

CONCRETE BY PUMP AND PIPELINE

- The most efficient method of placing concrete.
- Life of Pump practically indefinite: all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE REGISTERED TRADE MARK OF

PUMPCRET


THE CONCRETE PUMP COMPANY LIMITED

THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone : Western 3546

Telegrams : Pumpcret, Kens, London



Reconstruction of Whitehills Harbour

by
THE
YORKSHIRE
HENNEBIQUE

Contracting Company Limited

Established 1904

CIVIL ENGINEERING CONTRACTORS

HENNEBIQUE HOUSE

YORK

Telephone: York 54656 (4 lines)



the modern method of



PRESTRESSED CONCRETE DESIGN AND CONSTRUCTION

**FOR
INSITU AND
PRECAST
STRUCTURES
OF ALL TYPES**


This system is described and illustrated in our Catalogue, together with some of the many important contracts on which it has been used. Engineers and Contractors interested in the latest developments should send for a copy.

THE PZ PRESTRESSING CO. LTD.

BURCOTT LODGE, BURCOTT, WING, LEIGHTON BUZZARD.

TELEPHONE: WING 286

"I wonder if
'417' CEMENT
is right for
the job...?"



...Let's see. That new road is due to be laid in late February...there might be a freeze up, so ordinary cement wouldn't set or harden in time ...'417' acts fast enough to get over that problem—but will its final strength be high enough? Better ask the people who make it...save a lot of time and trouble in the end.

'417'
CEMENT



'417'—quick-setting and rapid hardening—is an accelerated B.S.12 Portland Cement and therefore gives excellent ultimate strength and durability. Use it with confidence for all cold weather road work and non-stop repair or maintenance jobs.

See CMC about Cement!

Make use of our technical service. For all information please write to:

THE CEMENT MARKETING COMPANY LIMITED, PORTLAND HOUSE, TOTTHILL STREET, LONDON, SW1 • Telephone: TAY 3456
G. & T. EARLE LIMITED, NULI • Telephone: NUL 28121

Selling Organisations of The Associated Portland Cement Manufacturers Ltd



RANALAH STEEL MOULDS

have cut our costs again
—AND THEY GIVE A BETTER FINISH



Have you a concrete
production problem
to discuss? Then please
visit us at the
Building Exhibition
Row T Stand 301

RANALAH

STEEL MOULDS LIMITED

THE HYDE · LOWER BEVENDEAN · BRIGHTON · SUSSEX Tel: 62216-7-8

Another
job
GLEESON
are
proud of...



Fleetwood Promenade and Sea Wall

The guide-book says: 'Fleetwood is proud of its promenade—and rightly so. It offers uncluttered views, spacious lawns with leisurely walks along the outer promenade without the worries of traffic...'

A section of the Sea Wall is but one of the many jobs in civil and constructional engineering of which Gleeson are proud. Others include power stations, factories, multi-storey flats, bridges, railway improvement, road development and coast protection schemes.

GLEESON

*Consulting Engineers:
Lewis and Duvivier, London*

*Constructed for the Municipal
Borough of Fleetwood.*

M. J. GLEESON (Contractors) LIMITED

Haredon House, London Road, North Chisam, Surrey

Telephone: Fairlands 4321

TA6535

INSEPARABLE from REINFORCEMENT



... OF COURSE!

and a guarantee that
the specified concrete cover
is accurately maintained . . .

Complying in ALL respects to the British Standard & Codes of Practice. The U-KLIPON BAR SPACER of revolutionary design is instantly fixed with a vice-like grip in the desired position on all types of reinforcement, including mesh and prefabricated. As an inseparable part it positively cannot be displaced by heavy tamping or vibrating. For any Bar Spacing problem,

CONSULT

THE B.E.C. BAR SPACER SERVICE

which has been and is responsible for the most outstanding and prominent contribution to accurate bar spacing in reinforced concrete, thus providing precision, economy, and labour-saving means of ensuring that the specified concrete "cover" is maintained under all conditions. It is noteworthy that such is the increasing popularity and demand for "B.E.C." Bar Spacers, borne out by sales in excess of 35 millions, that we are able to RETAIN OUR PRICE LIST OF 1945 WITHOUT MODIFICATION. Over 120 stock sizes of bar spacers enable us to give immediate attention to requirements. Write now for comprehensive details and samples. Our Technical Consultants will call on request.

Patent Nos. 597,505, 715,563, 789,018, 818,538.

Registered Nos. 870,560, 886,239. English and foreign patents pending.



B.E.C. BEARER BLOCK

FOR GROUND BEAMS • BARREL ROOFING
BRIDGES • MAT WORK • ETC.

The "B.E.C." precision-made bearer block is another inexpensive B.E.C. aid to obtain accuracy with speed in concrete construction. Let us send you full details.

BERRY'S ENGINEERING CO.

SOLE MANUFACTURERS:

Middle Road, Shoreham-by-Sea, Sussex

Phone and Grams: Shoreham-by-Sea 3541-2

CONTRACTORS TO MINISTRY OF SUPPLY, ETC., ETC.

Enhance your Prestige.
Specify and use with
confidence.

Boosting storage space capacity—the high-speed **HYSTER** truck moves and stacks faster and more smoothly.



Model YE40

Photo by courtesy of Holland & Hannen and Cubitts (Great Britain) Ltd



Hyster **SpaceSaver** Lift Trucks from 1,000 lb. to 10,000 lb. capacity: Challenger Lift Trucks from 1,000 lb. to 46,000 lb.; diesel, L.P.G. or petrol. Hyster Ransomes—Electric Lift Trucks from 1,000 lb. to 6,000 lb. capacity, with complementary range of cranes, towing tugs, platform trucks, reach trucks, straddle trucks, hydraulic and mechanical attachments.

'Hyster' and 'Space-Saver' are Registered Trade Marks

The Authorized Hyster Dealers

A. H. MASSEI, LIMITED

CALEDONIAN MECHANICAL HANDLING CO. LTD

FRED MYERS LIMITED

LEVERTON (Industrial) LIMITED

East Wall Road, Dublin, 1. Telephone: Dublin 78891

Branch office: 4, Southwark Square, Bedford. Telephone: Bedford 2888

21, Old Castle Road, Glasgow, S.A. Telephone: Maryle 2334/4

Branch office: Larnell, Perth.

Vale Road, Windsor, Berks. Telephone: Windsor 389

Branch offices, Service depots: London, Cardiff, Windsor, Brentwood, Birmingham, Loughlin (Staffs).

Headquarters Road, Rotherham. Telephone: Rotherham 78759

Branch depots: Newcastle, Wigan and Salford.



**MONCRIEFFE
CHURCH OF SCOTLAND
EAST KILBRIDE
LANARKSHIRE**

When this fine church was built 'Pudlo' Waterproofing was used in all cement work below ground level. Mix: 5 lb. 'Pudlo' to 1 cwt. cement.

See us on Stand C Row J
The BUILDING EXHIBITION
OLYMPIA, 15-29 NOVEMBER



The word 'PUDLO' is the registered Trade Brand of Kerner-Greenwood & Co. Ltd., by whom all articles bearing the Brand are manufactured.

Architects: Ross, Doak & Whitelaw, 2 Clifton Street, Glasgow C.3.
Contractors: A. M. McDougall & Co. Ltd., Davaar Street, Glasgow E.2.

Quietly and efficiently 'Pudlo' cement Waterproofing Powder plays its part in all manner of building projects throughout the world—from underground reservoirs in Gibraltar to mansion blocks in Hong Kong, from power stations in Europe to the modern church illustrated above. For more than fifty years 'Pudlo' Brand Waterproofing has maintained its reputation in the most searching conditions. 'Pudlo' can be used either to retain or exclude water in all types of concrete structures; our technical service is at your disposal and free advice may be had on any individual waterproofing problem.


CEMENT WATERPROOFING POWDER

OTHER 'PUDLO' PRODUCTS INCLUDE: Waterproof Cement Paints, Cement Paint Primer, External Water Repellent, Cement Bonder, Plaster Bonder, Frost Protector/Rapid Hardener, Mortar Plasticiser, Cement Hardener/Dust Proofer, 'Feusol' Fire Cement. Concrete Plasticiser and Permanent Colours for Cement.

KERNER-GREENWOOD & CO. LTD., KING'S LYNN, NORFOLK

WT.19

Telephone: King's Lynn 2293



Opening up new horizons

RYLANDS HIGH TENSILE PRESTRESSING WIRES chosen for the wonder city of **BRASILIA**



PLAN OF BRASILIA

This city in the interior, built to stimulate Brazil's prosperity, has cost an estimated 345 million dollars. From a central intersection the ultramodern planning extends to the president's palace built on the shores of one of the largest man-made lakes in the world.

Acknowledgements:

Structural Engineer:

Sergio Marques de Souza, Rio de Janeiro.

Contractors:

Construtora Rabello S.A., Rio de Janeiro.

Wire supplied through:

Adams & Harvey Ltd.,

London and Associates in Brazil.

The words wire and Rylands have been synonymous in the building of countless new constructions all over the world. Its use in the erection of Brazil's new capital proved again that Rylands can meet any demand for standard and specialized high tensile wire needed in prestressed concrete projects everywhere.

In one of the most daring concepts of architecture in this century, Rylands again upheld their reputation by supplying tons of high tensile steel wire for prestressing concrete beams in the city centre intersection flyover; and for the Tocantins Bridge, one of the largest single span prestressed concrete bridges in the world.

Whether your order for prestressing wire is large or small, consult Rylands.


RYLANDS

BROTHERS LIMITED
WARRINGTON LANC.



AB MOULDS

**CAN BE RELIED UPON TO
GIVE CONSISTENT SERVICE
OVER MANY YEARS**



The above illustration of a standard garden edging mould shows the tough construction of our moulds, which reduces expenditure on maintenance and constant replacement of moulds of less robust design.

A. B. MOULD & CONSTRUCTION CO., LTD.

**VULCAN WORKS, VULCAN WAY
NEW ADDINGTON, SURREY**

Telephone : Lodge Hill 2347

Telegrams : Abmould, Croydon

UNDERPINNING

RETAINING

CONSOLIDATING

PALI RADICE (ROOT-PATTERN PILES)

SYSTEMS PROVIDE THE CONCRETE ANSWER

There is a Pali Radice system of structural protection for foundations against any kind of underground movement. Patented systems of root pattern piles provide a most effective means of underpinning any building or structure, while our patented grid retaining wall system ensures the stability of existing structures during nearby deep excavations. The reinforcing action is very smooth and gradual and starts from the beginning of the work. Consolidation for upper structures does not interfere with the original room disposition and preserves existing artistic decorations, frescoes, mosaics, etc. Other patented methods are applied to the consolidation of various types of ground, and for the formation of water-tight diaphragms by casting reinforced concrete walls in the ground.

Our extensive experience, and our constant development of new methods, enable us to tackle with confidence any problem connected with this type of work, however difficult or tricky the situation, and wherever it may be.

Soc An FONDEDILE INC

NAPLES—Via Verdi 35.
GENOA—Via Milano 40c.
PALERMO—Via E. Amari 32.
MILAN—Via Velasca 5.
ROME—Piazza Buenosaires 14.
ATHENS—12 Kolokotroni Str.
VIENNA—Strarkfriedgasse 25.

All enquiries in the U.K. to—

OVERSEAS COMMODITIES (SOC) LTD
2 LONDON WALL BUILDINGS, LONDON EC2 Tel: London Wall 5276

LACO BAR BENDING AND CROPPING MACHINES

The LACO BAR BENDERS

are made in capacities up to 2" diameter. Several bars can be bent simultaneously.

MAIN FEATURES

Model LB.900


Two turntables revolve simultaneously. The fast at more than 10 r.p.m. enabling a 1" hook to be bent in 3 seconds.

Feeding: Bars are fed into the machine from left or right; hooks are made clockwise or anti-clockwise.

Automatic Stop: Turntables can be set to stop automatically at any angle to an accuracy of $\frac{1}{8}^{\circ}$.

Maintenance negligible. All bearings are ball or roller throughout. Gears are of steel and precision cut. All shafts, even the slowest, are fitted with grease-packed ball bearings.

Fitted with either electric motor, gasoline engine or diesel engine.



The LACO BAR CROPPERS

in all capacities up to 2" diameter, provide the quickest and safest method of site cropping.

MAIN FEATURES



Oil is circulated in closed circuit and, whilst machine is in operation, abundant positive lubrication is assured.

No damage results from lack of oil and no special servicing required. If foot pedal is depressed when no bars are placed between cutting blades, the blades will automatically stop, thereby assuring a very important safety feature because no cut can be made involuntarily. NO OPERATOR HAS EVER BEEN INJURED BY THESE MACHINES. Machines available at prices lower than any other manufacturer in the World. Capacities from $1\frac{1}{2}$ " up to 2" diameter.

SEE OUR STAND NO 728 ROW N IN THE NATIONAL HALL AT THE BUILDING EXHIBITION OLYMPIA NOV. 15-20.


PROMPT DELIVERY AVAILABLE

Full details from

LAWLER AYERS & CO LTD

Broad Street House, 54 Old Broad Street, London, E.C.2

Telephone: London Wall 6331



for
economy in
bored foundations

DOWN TO 110 FEET

McKINNEY

- * Underreamed
- * Greater bearing area
- * Fewer piles
- * Reduced costs

*May our design engineers assist you with
your foundation problems?*

A **LAING** COMPANY

McKINNEY FOUNDATIONS LIMITED

Elstree Way, Boreham Wood, Hertfordshire. Tel: Elstree 4022

PSR* SEALERS

KELSEAL manufacture a tremendous range of Sealing materials designed to suit various applications in a variety of industries.

Experience gained from solving problems concerning the effective sealing of reservoirs, dams, motorways, piles and "metal to concrete" structures has proved the value of our P.S.R. (Polysulphide Synthetic Rubber) sealers and primers.

The large permanent range of Jointing compounds include Butyl Rubber and Epoxy 2-part compounds.


We will be pleased to supply technical information concerning your particular sealing problems.

* *Polysulphide Synthetic Rubber*

**Watertight answer
to Concrete Sealing
Problems!**

KELSEAL LTD., VOGUE HOUSE, HANOVER
SQUARE, LONDON, W.1 • Hyde Park 1411

KELSEAL



BUILD ON A SURE FOUNDATION

The modern piling techniques and systems of Simplex are backed by over half a century of experience. Schemes and quotations for piling or reinforced concrete foundations will be gladly supplied, without obligation, on request.



7 Lyon Place, Grosvenor Gardens, Westminster, London S.W.1. Tel: SLOane 9122/3/4

STORER'S



Sawing, Planing and Moulding Mills and Storage Yards at Barking

for SOFTWOOD


Wm. T. STORER & CO. LTD.

Timber Importers and Merchants

ESTABLISHED 1913

Telephone: RlPpleway 0301 (10 lines)

RIVER ROAD - BARKING - ESSEX



One of the Land-Rover fleet at Stewarts and Lloyds' Corby Steelworks.



By Appointment
to Her Majesty Queen Elizabeth II
Manufacturers of Land-Rovers
The Rover Co. Ltd.

... The 4-wheel drive Land-Rover. As familiar to the cooling tower and the rolling mill as to the cattle and the sheep... Land-Rovers. No vehicles are better fitted to ride smooth-shod over the worst of surfaces, or to fetch, carry and haul with precision and authority. You can tell by the famous names they wear what faith the world of Industry has in them. Ask your Distributor or Dealer for a Land-Rover demonstration.

**There's no substitute
for the 4-wheel drive**




**Petrol
or
Diesel**

THE ROVER COMPANY LTD • SOLIHULL • WARWICKSHIRE also DEVONSHIRE HOUSE • PICCADILLY • LONDON

CNS-289

PSC

HYDRADUCT SHEATH



HYDRARIGID

HYDRARIGID


HYDRAFLEX

Hydraduct is an extremely robust form of sheathing for prestressing tendons and meets the most stringent requirements of Designers and Contractors; problems which may be encountered in transportation and site handling have been carefully considered.

PSC GROUT INJECTION EQUIPMENT



◀ P.S.C. hand-operated diaphragm, direct displacement grout pump with electrically operated stirrer.



P.S.C. power-operated grout injection pump. ▶

The subject of cable grouting is one that P.S.C. Equipment Limited have studied intensively and for which a range of equipment has been developed.

PIONEERS OF PRESTRESSED CONCRETE IN GREAT BRITAIN

P.S.C. Equipment Limited, members of the Freyssinet International Organisation, have available a range of prestressing systems including Freyssinet MultiWire, Freyssinet MultiStrand—FreyssiStrand, P.S.C. MonoWire, P.S.C. MonoStrand and P.S.C. Pretensioning. Full detail and complete technical information are always available on request.

FREYSSINET


RUBBER BRIDGE-BEARINGS



... the modern method of supporting bridges and other civil engineering structures. They are more economical and technically superior to traditional steel bearings and are widely recommended. Freyssinet bearing pads are of unit bonded construction. The design of the pads is based on the relationship between loads, displacements and rotations, and, as no moulding is required, each case is treated as unique and the proposed pad calculated accordingly. The highly satisfactory behaviour of this type of pad has been proved by tests and by observation on over 500 bridges on which they have been used. Technical questionnaire forms are available on request.

FREYSSINET

FLAT JACKS



Ref.	Outside Diameter (inches)	Maximum Force (tons) at 2,000 lb./in. ²
07	2.75	3
12	4.72	9
15	5.90	17
22	8.66	41
25	9.84	54
27	10.6	64
30	11.8	81
35	13.0	114
42	16.5	168
48	19.7	245
60	23.6	357
87	34.2	772
92	36.2	866


These hydraulic jacks of unusual and unconventional design permit enormous forces to be exerted where the movement required is small. They have considerable application in underpinning, levelling, and thrust control in engineering structures.

PSC



EQUIPMENT LTD

HEAD OFFICE AND WORKS: ARUNDEL ROAD, INDUSTRIAL TRADING ESTATE, UXBIDGE, MIDDLESEX
 Telephone: Uxbridge 35241



Circular tipping skips 1½ cu. ft. to 3 cu. yd.

ABELSON for SKIPS

ABELSON

& CO. (ENGINEERS) LTD.

SHELDON BIRMINGHAM 26

TELEPHONE: SHELDON 2424 (10 lines)

Special and non-standard skips manufactured to your specifications



Circular controlled discharge bottom dump skips 1 cu. yd. to 1 cu. yd.

Roller skips 1 cu. yd. capacity.




Concrete pouring skips side dis. large 10 cu. ft. to 27 cu. ft.



Rest skips 3 cu. ft. to 7 cu. ft.



Concrete pouring skips holding discharge 10 cu. ft. to 27 cu. ft.



Square tunnelling skips 4 cu. ft. to 10 cu. ft.



GUNITE SPECIALISTS

WM. MULCASTER & CO. (CONTRACTORS) LTD.

We invite inquiries for Gunite Linings and Renderings for new or old structures of every kind in any part of the country.

HASLINGTON

Telephone: CREWE 2265-4

CREWE

build to

New Chemical Building for Joseph Crosfield & Sons Ltd., Warrington.



your satisfaction..

New Administration Block for Shell Refining Co. Ltd. Stanlow.



specification..

New Food Factory for the H.J. Heinz Company Limited at Wigan. The largest Food Factory in Europe and the British Commonwealth.



and .. on time!

Whatever the project, its size or function Monk are best equipped to build to your complete satisfaction.

From the planning stage throughout every phase of uninterrupted construction, Monk capacity expedites progress to economic completion.

Monk

A. MONK & COMPANY LIMITED
Warrington and London
Offices at: Hull, Middlesbrough and Stamford

BUILDING, CIVIL ENGINEERING AND REINFORCED CONCRETE CONTRACTORS

Bp BOLTS & NUTS TIE-RODS ETC.

FOR THE CONTRACTOR



Manufactured by

B. PRIEST & SONS LTD. OLD HILL STAFFS. ENG.

Telephone: Cradley Heath 66501 (8 lines)

THE LEEDS OIL & GREASE CO.

CONCRETE MOULD OIL

CHADWICK ST. LEEDS.

PUT YOUR FAITH IN THE TESTED BRAND


THIS LABEL ON EVERY BARREL CARRIES WITH IT FIFTY YEARS' EXPERIENCE OF MANUFACTURE.

NONE OTHER IS "JUST AS GOOD"

THE LEEDS OIL & GREASE CO.

Phone 22480 LEEDS, 10 'Grams: "Grease, Leeds 10"

Foundation cylinders by BRAITHWAITE



160 Braithwaite bored cylinders support the seaward section of the dry dock at Trieste, Italy. The barge mounted Braithwaite borer used for the project is also illustrated.

General Contractor: *Impresa Pietro Cidonio, Rome.*



**BRAITHWAITE FOUNDATIONS
& CONSTRUCTION LIMITED**

(Proprietors: Braithwaite & Co. Engineers Limited)


London Office:

DORLAND HOUSE • REGENT STREET • SW1

Telephone: WHItEhall 3993

Telegrams: BROMKIRK LONDON SW1. Telex: 23320





Slide filling moulds for manufacturing 24" diameter by 3' effective length O.G. pipes.

Further details and quotations sent on request

Moulds and formwork

for the concrete industry

A service to the industry ranging from the small equipment illustrated to complete spinning plants, backed by years of technical experience.

We are now operating from our extensive new premises at the address below.

Coneybeare

THE ORIGINAL PIPE MOLDERS

Coneybeare & Co. Ltd., Torrington Road, Ashford, Kent. Tel: Ashford 545/6

COPPER STRIPS

for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.



ALEX J. CHEETHAM LTD.

MORTON STREET • FAILSWORTH • MANCHESTER

Telephone: FAILsworth 1115/6

DS.14

Colcrete

GROUTED CONCRETE CONSTRUCTION . . .



Gammon India have used the Colcrete Process for construction of the Brahmani Pick-up Weir, near Rourkela, and, in partnership with Hochtief A.G. Essen, for much of the foundations in the steelworks being erected for Hindustan Steel Ltd. at Rourkela.

Gammon India have recently obtained a contract for the construction in Colcrete of the great Mundali Weir, which will cost some £1,500,000.

Colcrete is the product of the colloidal grouting process, invented by Mr. John C. Gammon with the late Mr. J. S. Morgan, whereby a grout of cement and sand is injected into stone.

COLCRETE LIMITED

STROOD • ROCHESTER • KENT

Phone: Strood 78431/2/3. Grams: Groutcrete, Rochester




Illustration above shows some of the post-stressed bridge beams, each 80 ft. long and weighing 35 tons, produced by Anglian Building Products Ltd., for British Railways, Midland Region. Main Contractors: Messrs. Leonard Fairclough Ltd.

80 - ft. BEAMS
cast in
WOODEN
MOULDS
supplied by

MAY & BUTCHER

(1961) LIMITED


SPECIALISTS IN TIMBER SHUTTERS AND MOULDS FOR CONCRETE

More and more Contractors and Precast Concrete Makers in all parts of the country are taking advantage of the first-class service we offer in the supply of timber shutters and moulds to any design and size. This service has proved over and over again that by ordering your shutters and moulds from us you effect every possible saving in time, labour and money. However intricate the shutter or mould, you are assured of accuracy in every detail and a product with long trouble-free life. Shutters and moulds can be supplied with a plastic lining if desired. Full details of this class of work carried out by us are available on request.

HEYBRIDGE BASIN, MALDON, ESSEX.

TELEPHONE: MALDON 698/9

THE MACALLOY END PLATE



End plates are similar (though not identical) for both wedge and threaded end anchorages and are of a size and thickness to remove any doubt about distortion under load. Two $\frac{1}{2}$ " holes drilled on the diagonal $3\frac{1}{4}$ " apart are provided to secure the plate positively and accurately in the formwork. Using a grouting flange behind the plate, one of the holes serves as an entry for grout or an air escape hole and at the same time the flange conveniently accepts the bar sheath to which it can be sealed without difficulty. The end plate and the grouting flange are both included in the cost of a standard end anchorage.

The standard sizes are for threaded ends:

$1\frac{1}{4}$ " diameter bar	(55T)	6"	sq. x 2"	thick
$1\frac{1}{2}$ " "	(45T)	5 $\frac{1}{2}$ "	sq. x $1\frac{1}{2}$ "	"
1" "	(35T)	5"	sq. x $1\frac{1}{2}$ "	"
$\frac{7}{8}$ " "	(27T)	5"	sq. x $1\frac{1}{8}$ "	"

and for wedges:

$1\frac{1}{4}$ " diameter bar	(55T)	7"	sq. x 2"	"
$1\frac{1}{2}$ " "	(45T)	6"	sq. x 2"	"
1" "	(35T)	5"	sq. x $1\frac{1}{2}$ "	"
$\frac{7}{8}$ " "	(27T)	5"	sq. x $1\frac{1}{8}$ "	"

Special sizes of plates can be provided but they may of course take a little longer to produce, especially when we are very busy.

McCALLS MACALLOY LIMITED

TEMPLEBOROUGH • SHEFFIELD • ENGLAND • P.O. BOX 41


Telephone: ROTHERHAM 2076 (P.B. Ex 0 lines)

LONDON: SLOANE 0428 • BIRMINGHAM: ACOCKS GREEN 0229

PORTSMOUTH: COSHAM 78702 • MANCHESTER: BLACKFRIARS 1018

PC70

PRESTRESSING
STEEL
by **McCALLS**



For compacting mortar cubes
for compression tests to

B.S. 12/1958, 146, 1370, etc.

Automatic Time Control

"CAPCO"

H.F. VIBRATOR

"CAPCO" CONCRETE TESTING APPARATUS also includes:
Cube Moulds; Slump Cones; Tensile, Vicat and Cylindrical
Moulds; Compacting Factor Apparatus—Standard and Auto-
matic; Sieve Vibrators and Sieves; etc.

CAPLIN ENGINEERING CO. LTD

(ESTABLISHED 1918)

POLLEN HOUSE, 18/12 CORK STREET, LONDON, W.1

Phone: REGENT 0716. Grams: CAPLINKO, LONDON. Telex: 23255. Cable: CAPLINKO, LONDON. Works: IPSWICH.

LENSCRETE LTD

maximum light minimum cost


LITEX roof lights give a very high transmission of light—up to 92%—and are easily and quickly handled and fitted. A full range of standard form metal ventilators, curbs and liners are available for use with LITEX roof lights.



LITEX spherical roof lights


Litex LAMINATED FIBREGLASS roof lights

LITEX roof lights with their glass fibre reinforced construction can be used with advantage in many places where conventional lights would be impracticable or too costly. Virtually unbreakable, heavy packing is unnecessary allowing quick and easy handling on site.



LITEX rectangular roof light

LITEX roof lights are ideal for use in schools, hospitals and other buildings where absolute safety is required—they will not shatter and cannot support combustion. The plastic will not creep, nor become brittle with age or very hot temperatures.




LITEX lantern lights

LITEX roof lights are not attacked by smoke or fumes from most industrial processes, and may safely be used in factory and workshop buildings.

For further information about LITEX roof lights please write to

LENSCRETE LIMITED Queens Circus London SW8 telephone MACaulay 10

*a proven material
with a **BIG IMPACT**
on design*




FILIGREE by **HEAD WRIGHTSON**

For fast low cost floor construction the patented filigree welded steel joist offers many advantages.

Produced automatically, supplies are available at short notice, and the light weight of this strong reinforcement girder facilitates transport to site.

Designed for use with hollow block, hollow tile and cast in situ floors, filigree offers

- ★ A light but strong girder of consistently high quality.
- ★ Speedier and easier construction.
- ★ Availability in three depths.



We should welcome a visit from you, but if you cannot arrange this, please write or phone for more information to

the Sales Manager FILIGREE DIVISION

HEAD WRIGHTSON TEESDALE LTD

TEESDALE IRON WORKS • THORNABY-ON-TEES • TEL: STOCKTON 62241





IBECO

WATERPROOF PAPER

IN CONCRETE ROAD CONSTRUCTION

Recommended qualities for concrete work are IBECO No. 40 to BS 1521/1949 Class B and IBECO No. 60, the choice depending on the stresses involved. The former fully meets the specification at the lowest possible cost. As well as preventing seepage from the mix IBECO also checks the upward penetration of harmful acids and other chemicals frequently occurring in subsoils. It also has useful applications as a curing overlay. There is no free bitumen in IBECO to sweat out under exposure to hot sun. We will gladly send samples on request.

DAVIDSON'S PAPER SALES LTD.

LONDON: 82/84 St. John St. E.C.1 LIVERPOOL: 31 North John St. 2. LEEDS: 9 Albion St.

NEWCASTLE: 42 Corporation St. GLASGOW: Laird Place, Bridgeton, SE.

EDINBURGH: Boroughloch Square. DUNDEE: 24 Lamb's Lane. ABERDEEN: 4 Trinity Quay.

HEAD OFFICE: Mugimoss Mills, Bucksburn, Aberdeen.

For the essential retention of water in a concrete mix to ensure sound setting and hardening, careful contractors are more and more depending on IBECO... Like no other waterproof paper, IBECO is waterproof *throughout its texture*. The proofing bitumen is part of the paper itself. Folding, creasing, even heavy trampling will not impair IBECO's impermeability... It's easy and quick to handle:—speeds the work as well as lowering its cost and ensuring a better job.

Remember IBECO for contracts in hand and in prospect.

WHARFE BRIDGE at WETHERBY illustrates aesthetic design

Agent Authority:
The County Council of the
West Riding of Yorkshire
Engineer:
S. Meynard Lovell,
O.B.E., F.R.D., T.D.,
Chartered Civil Engineer.
Contractors: Crowley,
Russell and Co. Ltd.
*Sub-Contractor for the
Wharfe Bridge:*
The Cementation Co. Ltd.



The Wharfe Bridge carrying the Wetherby By-Pass over the River Wharfe at Wetherby is of balanced cantilever and suspended span construction, with two side spans each of 96 ft and a central span of 160 ft—the length of the cantilevers being 45 ft each with a suspended span of 70 ft. Approved by the Royal Fine Art Commission, the design of the bridge has achieved harmony with a setting of considerable rural beauty. The 70 ft suspended span consists of fifteen I beams 5 ft 3 in deep, spaced at 4 ft 6 in centres, together with two reinforced concrete rectangular fascia beams, having curved soffits to accord with the soffit line of the cantilever arms.

The fifteen I beams are prestressed post-tensioned beams which were manufactured on site, and all cables were prestressed before erection except in the case of the outer I beams which were partially stressed before erection and finally stressed after construction of the deck slab.

After erection of the I beams, transverse diaphragms were cast between the beams and prestressed through straight cables.

Prestressing of the beams and diaphragms was on the Gifford-Udall system and 0.276 in diameter wires were used throughout.

For further details on this project please write for leaflet.

wire was essential—

Johnson's of course!

Richard Johnson & Nephew Limited, Manchester 11. Telephone East 1431



IBECO

WATERPROOF PAPER

IN CONCRETE ROAD CONSTRUCTION

Recommended qualities for concrete work are *ibeco* No. 40 to *ibeco* 1521/1949 Class B and *ibeco* No. 60, the choice depending on the stresses involved. The former fully meets the specification at the lowest possible cost. As well as preventing seepage from the mix *ibeco* also checks the upward penetration of harmful acids and other chemicals frequently occurring in subsoils. It also has useful applications as a curing overlay. There is no free bitumen in *ibeco* to sweat out under exposure to hot sun. We will gladly send samples on request.

For the essential retention of water in a concrete mix to ensure sound setting and hardening, careful contractors are more and more depending on *ibeco*... Like no other waterproof paper, *ibeco* is waterproof throughout its texture. The proofing bitumen is part of the paper itself. Folding, creasing, even heavy trampling will not impair *ibeco*'s impermeability... It's easy and quick to handle—speeds the work as well as lowering its cost and ensuring a better job.

Remember *ibeco* for contracts in hand and in prospect.

DAVIDSON'S PAPER SALES LTD.

LONDON: 82/84 St. John St. E.C.1 LIVERPOOL: 31 North John St. 2. LEEDS: 9 Albion St.

NEWCASTLE: 42 Corporation St. GLASGOW: Laird Place, Bridgeton, SE.

EDINBURGH: Boroughloch Square. DUNDEE: 24 Lamb's Lane. ABERDEEN: 4 Trinity Quay.

HEAD OFFICE: Mugiemoas Mills, Bucksburn, Aberdeen.

WHARFE BRIDGE at WETHERBY illustrates aesthetic design

Agent Authority:
The County Council of the
West Riding of Yorkshire
Engineer:
S. Maynard Lowell,
O.B.E., E.R.D., T.D.,
Chartered Civil Engineer.
Contractors: Crossways,
Russell and Co. Ltd.
*Sub-Contractor for the
Wharfe Bridge:*
The Cementation Co. Ltd.



The Wharfe Bridge carrying the Wetherby By-Pass over the River Wharfe at Wetherby is of balanced cantilever and suspended span construction, with two side spans each of 96 ft and a central span of 160 ft—the length of the cantilevers being 45 ft each with a suspended span of 70 ft. Approved by the Royal Fine Art Commission, the design of the bridge has achieved harmony with a setting of considerable rural beauty. The 70 ft suspended span consists of fifteen I beams 5 ft 3 in deep, spaced at 4 ft 6 in centres, together with two reinforced concrete rectangular fascia beams, having curved soffits to accord with the soffit line of the cantilever arms.

The fifteen I beams are prestressed post-tensioned beams which were manufactured on site, and all cables were prestressed before erection except in the case of the outer I beams which were partially stressed before erection and finally stressed after construction of the deck slab.

After erection of the I beams, transverse diaphragms were cast between the beams and prestressed through straight cables.

Prestressing of the beams and diaphragms was on the Gifford-Udall system and 0.276 in diameter wires were used throughout.

For further details on this project please write for leaflet.

wire was essential—

Johnson's of course!

Richard Johnson & Nephew Limited, Manchester 11. Telephone East 1431

★ **WATERTIGHT LININGS FOR RESERVOIRS, SWIMMING POOLS, ETC.**

WE ARE SPECIALISTS IN THE REPAIR AND RECONDITIONING OF REINFORCED CONCRETE STRUCTURES ★ **LININGS FOR TUNNELS, SEWERS, TANKS, ETC.**

GUNITE
CONSTRUCTION CO LTD
WESTERN HOUSE, HITCHIN, HERTS.

TELEGRAMS:
'GUNITE,
HITCHIN'

TELEPHONE:
HITCHIN 4371



REINFORCEMENT SERVICE *including* SUPPLY & BENDING


We are manufacturers of mild steel bars for reinforced concrete, and have every facility for supplying bars cut to required lengths. We also bend ready for fixing if desired for contracts in any part of the country. Include our name on your list for future reinforcement requirements.

WALKER WRIGHT & CO. LTD

DARNALL, SHEFFIELD, 9

TELEPHONE: 41063-4-5

MILLIONS OF TONS OF TRAFFIC



WILL PASS OVER THIS BEAM

When finished, the spectacular $\frac{1}{4}$ -mile long Hammersmith Fly-over will contain 204 mammoth concrete beam segments weighing from 35 to 60 tons. These, together with a similar number of cantilever units of some 15 tons each, form the spine beam and ribs of this structure when jointed together and stressed. All have been cast by the contractors, Marples, Ridgway and Partners at their Heston casting yard, who selected Winget Vibrocon Poker Vibrators for the compaction of the high-grade dense concrete within the intricate moulds and complex reinforcements.

For maximum compaction use Winget 'Vibrocon' Poker Vibrators—the finest available today!

Client:
The London County Council

Consulting Engineers:
G. Maunsell & Partners
in association with
J. Rawlinson CBE., M.Eng.,
Chief Engineer LCC

Contractors:
Marples, Ridgway
& Partners Ltd.




Winget

LIMITED, ROCHESTER, KENT TELEPHONE STROOD KENT 78041 (8 LINES)

Whether it be an expansion
or construction joint—let . . .

DURAJOINT

take the strain



See what happens when the concrete contracts.

THE DURAJOINT

retains its close keying to the concrete beyond the flange nearest the centre. No other expansion joint gives this safeguard.

It takes care of shear as well!

Sole Manufacturers

DURATUBE & WIRE LTD


CENTRAL WAY (FAGGS ROAD), FELTHAM, MIDDX

Phone: FELTHAM 3453/6

Grams: DURATUBE FELTHAM



TAKE A GOOD LOOK AT THE SURFACE



The water tower illustrated has a protective Stic B stone covering stipple finish similar to that shown in the smaller photograph. Treated in this way it is completely protected from the atmosphere and will require no further attention for many years. Stic B can

be applied direct to new or old concrete and most other building surfaces. No other material affords such lasting protection, while remaining so easy to apply.

Descriptive literature available.

STIC B PAINT SALES LTD.

99 WANDSWORTH ROAD,

VAUXHALL, S.W.8

Telephone: RELiance 5566/2178 Telegrams: Sticbeslim, London, S.W.8

WHITLEY MORAN

AND CO. LTD



The North of England

GUNITE SPECIALISTS

BEHIND EVERY JOB . . . 25 years' experience in the scientific repair of engineering structures



5 OLD HALL ST. LIVERPOOL 3. PHONE: CENTral 7975/6
GRAMS: Gunite, Liverpool, 3

May we

PRECAST

your

STRUCTURAL COLUMNS

SAVE TIME and SAVE MONEY

J. A. KING & Co., LTD

181 Queen Victoria St., LONDON, E.C.4

Telephone: CENTral 5866 (5 lines)

Telegrams: Kinovique Cent London



Today's basic constructional material is concrete. It is used in roads, offices, factories, warehouses, and every conceivable kind of building. But to do its job with complete efficiency, concrete must be strengthened. And this is where Spencer Mesh comes in. Made to B.S. requirements, this electrically-welded mesh is made only from high tensile steel wire. Strong. Reliable. And what is more, the wire is drawn by the Spencer Wire Company themselves, in their own mill. Spencer Mesh is supplied in standard square or oblong meshes, in either sheets or rolls. If you have a concrete reinforcement problem, get in touch with the Spencer Mesh people. You can be sure of really useful help.

We are exhibiting at The Building Exhibition STAND 979-980
National Hall Gallery.

SPENCER MESH



SPENCER WIRE • WAKEFIELD



Telephone Wakefield 6111

D&W1161CCE

**The advanced method of weigh/batching and mixing
—rapidly becoming the most popular of 'on-site'
concrete preparation plant.**



*Ground-level
aggregate weigh/batching
and central mixing plants*



**STOCKPILING OF UNLIMITED AGGREGATE
QUANTITIES** ... continuous feeding by hand or
radial scraper ...

star compartments for 3 to 8 aggregates.

REMOTE CONTROL OPERATION ...
one man operated lever system.

ACCURATE WEIGHING ...
clear view weigh dial.

**DIRECT FEEDING OF CEMENT INTO
MIXER PAN** ...

high angle cement screw weigher.

HIGH OUTPUT QUALITY CONCRETE ...
'rota-forced' Waimar mixer.

CONCRETE STORAGE ...
remotely controlled hopper.

A.C.E. MACHINERY, LIMITED
PORDEN ROAD BRIXTON LONDON S.W.2

TELEPHONE: BRIXTON (3) 81115

GRAMS AUSEXON

TELEX 3101



**The NAME has changed—
but not the QUALITY**

Still by far the best workability aid for concrete, SEALOPLAZ gives high strength concrete at lower cost.

Yet it is not just a product—but a product and technical service combined. Technologists are available to visit your site, to help you get the best out of SEALOPLAZ.

Send now for details of the SEALOPLAZ service, particularly if you are interested in ready-mixed, pre-cast or pre-stressed concrete.



Sealocrete Products Ltd., Atlantic Works, Hythe Road, London, N.W.10.
Tel: LADBROKE 0015 P.B.E. Telegrams: Sealocrete Wesphone London.
Cables: Sealocrete London, N.W.10.



Model VP 350-A (Swivel Base or Barrow Mounting)

Prompt Delivery. Highly Competitive Prices. Genuine Service. Re-Sale Terms Available.

★ We operate a 48-hour Shaft Repair Service for all makes. Write to-day for 8-page fully descriptive Catalogue. Agents throughout the world.

30 years' experience in the design and manufacture of flex-shaft tools.

THE FLEXIBLE DRIVE & TOOL CO., LTD.

LONDON OFFICE: 17 QUEENSBERRY WAY, S.W.7. Telephone: KENSington 3544
Works at EDENBRIDGE, KENT, and THETFORD, NORFOLK

For Greater Strength, Firmer Bonding
and Better Surfacing of Concrete—

"BAXTON"

Regd. Trade Mark

British Made

Extra-High Frequency

INTERNAL CONCRETE VIBRATORS


● The model illustrated here operates at 5,000 to 15,000 Vibrations per minute from low flexible shaft speeds of 4,500 to 7,500 R.P.M.

● Petrol or Electric Drive.

● Robustly built throughout and backed by genuine service.

● Fitted centrifugal clutch, long-life flexible drive and Vibrator.

This unique machine, with quick-change additional tools, can also be used for: SURFACING, WET-RUBBING CONCRETE, GRINDING, DISC SANDING, AND DRILLING (up to 1½" in Concrete, 1" in Steel, and 2" in Wood).



**Precast
REINFORCED
CONCRETE
frames**



✱ Industrial buildings designed, supplied and erected by

STUARTS

GRANOLITHIC CO. LIMITED

ESTABLISHED 1840

REINFORCED CONCRETE
INDUSTRIAL FLOORS
RECONSTRUCTED STONE

LONDON ADDRESS: 14 College Road, Harrow. Tel: Harrow 8161-2-3

BIRMINGHAM: Northcote Road, Stockford. Stockford 3631-2. EXETER: 6-8 Melbourn Street. Exeter 73648.
EDINBURGH: 49 Duff Street, Don 1381-2. MANCHESTER: Ashton Road, Bredbury, Stockport. Woodley 9877-4.

LILLINGTON'S NO. 1 Metallic liquid smooths the way for ATCO mowers



The new ATCO Service Branch at Marsh Barton, Exeter, is one of a chain spanning the country where anything from a quick service job on site or a major workshop overhaul can be tackled.

To render the concrete floors hard, waterproof, dust-free and able to withstand exceptionally heavy wear and tear, Lillington's No. 1 Metallic Liquid was the natural choice.

For fifty years architects have specified No. 1 Metallic Liquid, as the scientifically prepared admixture that makes concrete completely waterproof and dustless, as well as accelerating the setting time. No. 1 Metallic Liquid is a necessity for waterproofing cement renderings to walls and basements, mass concrete retaining walls, foundations, flat roofs and tanks. You can rely on Lillington's No. 1 Metallic Liquid to give complete satisfaction because IT IS THE ONLY PROOFER SOLD UNDER GUARANTEE.

FROM

5'-

PER GALLON

Special terms for
bulk contracts

Write for Booklet 56

LILLINGTON'S

No. 1 Metallic Liquid

GEORGE LILLINGTON AND COMPANY LIMITED

Willow Lane, Mitcham, Surrey. Tel: Mitcham 1066

ALL OUR PRODUCTS ARE SUPPLIED IN FREE CONTAINERS

AP 369



COROBAR

REGD TRADE MARK


COLD WORKED HIGH TENSILE REINFORCEMENT

**MILD STEEL &
HIGH TENSILE WELDED FABRIC**

**AN EFFICIENT SERVICE ASSURED IN DESIGN
SUPPLY, BENDING & FIXING**

**EDC (THE ENGINEERING, DESIGN &
CONSTRUCTION COMPANY) LIMITED**
REINFORCEMENT SPECIALISTS

OFFICES: ARDSHIEL HOUSE EMPIRE WAY WEMBLEY MIDDXX.
TELEPHONE: WEMBLEY 9474 TELEGRAMS: EDCON WEMBLEY



THE P.C.4 PUMPCRET CONCRETE PUMP

CONCRETE BY PUMP AND PIPELINE

Specifications:

Two Sizes	P.C.3	P.C.4
Capacities per hour, approx. . . .	20-24 cu. yd.	8-10 cu. yd.
Range:		
Horizontal, approx.	1500 ft.	1250 ft.
or Vertical, approx.	135 ft.	125 ft.
Pipeline	6" i.d.	4 1/2" i.d.
Power required: Electric or Diesel	45 h.p.	25 h.p.

FOR HIRE



THE REGISTERED TRADE MARK OF
THE CONCRETE PUMP COMPANY LIMITED


PUMPCRET HIRE COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546

Telegrams: Pumpcret, Kens, London

E



**Another
big job
on which**


THAMES-NOILPLY

SMOOTH 'NO-OIL' SHUTTERING

was used!

A. A. STUART & SONS (Contractors) LTD., were so well aware of the outstanding advantages of Thames-Noilply that they used it in large quantities for wall structures in the construction of the Aigas Dam on the River Beauly, Inverness-shire.

Thames-Noilply is a plywood shuttering faced with a special glossy plastic, which completely repels concrete and leaves surfaces superbly smooth. No shuttering gives such a smooth surface without oil as Thames-Noilply. The elimination of oil and labour quickly makes the use of Noilply well worth while. With reasonable care Noilply can be used many times without oiling, and then can still be used in the traditional way.



Photographs by courtesy of the North of Scotland Hydro Electric Board. Consulting Engineers: Sir William Halcrow & Partners.

Supplied only through trade channels.


THAMES PLYWOOD MANUFACTURERS LTD.
Harte Lane, Barking, Essex. Tel: R1Ppleway 5511

WESTWOODS

HI-LOAD BRIDGE BEARING

TAKES 600 TON LOAD

4" DIA. ROLLER, 24" LONG



Rolling parts made from steel to a special specification. Precision workmanship. A very compact roller bearing for heavy reaction. Completely enclosed in grease box. No maintenance required. Bearings designed to suit all loads and conditions.

Apply for further details:

JOSEPH WESTWOOD & CO LTD

Bridge and Constructional Engineers, Manufacturers of Mechanical Grabs, Pressed Steel Troughing and Sheet Metal Equipment. Steel Stock Holders.


NAPIER YARD MILLWALL LONDON E 14

Phone: EASt 1043

Cables: Westwood London

Grams: Westwood Easphone London

SCHMIDT



CONCRETE TEST HAMMER

for immediate non-destructive
determination of compressive
strength

O. A. VOLKMAN LTD
3 ST. AUGUSTINE'S ROAD,
BIRMINGHAM, 16
Telephone: Edgbaston 1353

Best Quality CONCRETE AGGREGATES *in all grades*


DELIVERED BY ROAD OR RAIL

WM. BOYER & SONS LTD

MEMBERS OF S. & G.A. of G.B.

ESTABLISHED 1810

IRONGATE WHARF, PADDINGTON, W.2
TELEPHONE: PADDINGTON 2034-6



... Precast Concrete Piles

Preferred by constructional engineers for their unchanging supremacy, Stent Precast Concrete Piles have proved their qualities wherever used. In standard sizes—12" x 12" (in lengths 15 ft. to 40 ft.) and 14" x 14" (lengths 15 ft. to 55 ft.). Other sizes made to order.

Write for full details

HARBOUR INDEX FILE NO 116

STENT R.C. PILES

STENT PRECAST CONCRETE LTD

Chequers Lane, Dagenham Dock, Essex. DOM 0971 (4 lines)

Testing concrete cubes on site


MILBANK-WELLS

**HYDRAULIC PRESS
AND CUBE MOULDS**

Immediate Delivery

Two Sizes: 4 in. and 6 in.

PRESSES and CUBE MOULDS
Testing to 16,000 lb. per sq. in. to
B.S. 1881.



Approved for
all Government
Contracts

IN USE
ALL OVER
THE WORLD

6-IN. PRESS
258 TONS

4-IN. PRESS
110 TONS

MILBANK FLOORS LTD

PRESTRESSED CONCRETE CONSTRUCTION

RIVER HOUSE, EARLS COLNE, ESSEX

Telephone: Earls Colne 410



PRESTRESSED FLOORS & ROOFS SPANS UP TO 40 ft
FRAME BUILDINGS ALL TYPES



THE MOST ADAPTABLE FRAME BUILDINGS
FOR INDUSTRY AND AGRICULTURE

SINGLE SPAN • MULTI SPAN • CANTILEVER


**GLASS FIBRE**

LIGHTWEIGHT MOULDS

*for all***Concrete Castings****I FLOORING****I PANELLING****I STAIRWAYS****I COLUMNS**

Our wide experience in catering for moulds for concrete constructional work of every kind has proved that a glass-fibre mould can be produced which is not only equal in strength to a mould made of any other material, but has additional advantages in producing an excellent surface finish, easier handling, and adaptable to any design.

ALL YOUR MOULD PROBLEMS SOLVED**D. A. MODELS LTD****108 WOODSTOCK ROAD LONDON W.4 TEL: CHISWICK 201**



200
cycles

ALLAM

INTERNAL VIBRATORS without flexible drives

Now fitted with overload and anti-single-phase switches.

This new internal vibrator dispenses with the use of flexible drives. It has a frequency of 12,000 r.p.m. which, combined with amplitude, provides exceptional compaction of very harsh mixes. Vibrators of varying sizes, together with single- and multi-tool generators (Petrol, Diesel, and Electric drives), make this the most versatile range of internal vibrators so far available. It is in full production, and has already proved of considerable value to Contractors, Builders, and Precast Concrete Makers. Complete details of these and the range of Allam Vibrating Equipment will be sent on request. **BUILDING EXHIBITION, OLYMPIA.** See the range of Allam Vibrating equipment on STAND 760, Row P.

E · P · ALLAM & CO. LTD.

LONDON: 132-135 Sloane Street, S.W.1. • Telephone: Sloane 9976 (5 lines)

Works: Southend-on-Sea Tel.: 525243


AGENTS & DISTRIBUTORS: Strangford Ltd., Belfast and Dublin; A. Gunn & Co. Ltd., Altrincham, Chas.; O. L. Davies Ltd., Port Talbot, Glam.; J. Lewis (Machinery) Ltd., Burslem, Stoke-on-Trent; Concrete Engineering Services, York-Road Industrial Estate, Wetherby, Yorks; John Raulstone Ltd., Newcastle-on-Tyne; W. R. Salwood Ltd., Chandler's Ford, Southampton; J. A. McKay & Co. Ltd., Glasgow; Modern Plant Sales Ltd., Oldbury, Birmingham; Ernest Doe & Son Ltd., Industrial Division, Ulling, Malden, Essex; Contractors Plant (Notts.) Ltd., 78 Nottingham Road, Stapleford, Nottingham.

Mr. Manager —

**Your
office
has
arrived**

This fully equipped portable unit is the modern answer to accommodation problems. Of attractive appearance, the Portakabin is delivered on site ready for immediate occupation.

Basic Price, £265 ex works. Decorated internally and externally complete with telescopic legs. Size 16' x 8'. Quantity discounts. Available for hire. Full details on request.



**it's ready
to move in**

it's a

Portakabin

**a new concept in
portable accommodation**

PORTASILO LTD.

**Home Sales Office: Lawrence Rd. Green Lane, Hounslow
Middlesex.**

Telephone: HOUnslow 6452/3

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume LVI, No. 11.

LONDON, NOVEMBER, 1961.

EDITORIAL NOTES

Concrete and Europe.

THE discussions taking place in political and commercial circles regarding Britain's proposed closer contact with Europe through the Common Market may not raise so many problems for the cement and concrete industries as for some other industries. Imports and exports of cement from or to the Continent do not represent a large proportion of the British cement trade. According to the statistics issued by the Organisation for European Economic Co-operation, the amount of cement exported in 1960 from the United Kingdom to countries in the European Free Trade Area was about a million tons out of a productive capacity of about fourteen million tons. In the same year the imports from this area were about 118,000 tons of cement and upwards of 300,000 tons of cement clinker. Liaison with European countries raises the question of the relative requirements of the national standards for cement. That these vary considerably, depending on the type of cement, is seen by perusal of the compilation of such standards published by Cembureau,¹ but in most respects Portland cements complying with British Standards are superior to their European counterparts. A brochure issued by a national newspaper states, in relation to the cement industry, that transport costs are a limiting factor but that the industry stands to gain if Britain enters the Common Market. On the other hand, it is stated, the reinforcement industry may "feel the pinch".

The amount of international trade in the expanding precast concrete industry of Great Britain is, on account of the nature of the product, likely to be very limited, but the possibility of interchange of design and constructional services is no doubt being explored in some quarters. A spokesman at a recent meeting of the Reinforced Concrete Association explained that by 1963, firms in all member countries of the Common Market will be free to submit tenders for major contracts within the area, and by 1967 the more difficult problem of the free interchange of professional services may also have been solved in theory, at least, if not in practice.

What is probably of equal importance to these commercial aspects in a closer association with Europe is the possibility of there being more uniformity of design practice within the area, a condition which can hardly leave practice in this country unaffected.

An indication of some of the problems, in addition to those related to units of measurement and systems of notation, has already been seen in the activities of the European Concrete Committee which was formed in 1953 mainly for the preparation of recommendations, standardised for all European countries, to provide engineers with simple methods of calculation based on a more thorough knowledge of the behaviour of concrete and steel. During the first six years of its work the Committee endeavoured to arrive at conclusions regarding mainly the basic principles and practical methods of the calculation of the ultimate resistance of members subjected to simple bending, eccentric compression and axial compression, taking into account such factors as the rate and duration of loading, the nature of the stresses and the geometrical shape of the section. A study of the phenomenon of buckling has resulted in a method whereby the effects of a bending moment added to the normal stress are combined in the ordinary calculation of the ultimate resistance. Consideration was given to cracking of members under working load taking into account the amount of reinforcement, the mechanical and geometrical characteristics of the bars and some other conditions. Consideration of deformation, and particularly the calculations of deflections, are also the subjects of practical recommendations mainly for common types of structures. The foregoing research was concluded by considerations of the safety of structures. Other problems under investigation include resistance to shearing forces, the behaviour of ordinary slabs and flat-slabs, bond, and the phenomenon of redistribution in statically-indeterminate structures.

Progress has been made with the preparation of a code of practice for reinforced concrete construction to such an extent that draft recommendations have been issued. The present publication includes two out of three parts relating to design, but observations on the contents are best withheld until the third part, which is to include comments and appendices, is available.

In addition to the consideration of the alliance of research and design practice, there are fundamental problems which have to be solved before international uniformity of practice can be obtained. Two such problems are the conception of what constitutes failure of a reinforced concrete member and the basis on which the strength of concrete should be established. The complexity of the former problem is realised when the various current views are considered. The German and Austrian authorities define failure as occurring when arbitrary limits of the contraction of compressed concrete and elongation of the reinforcement are exceeded. Another conception, which is notably that of French engineers, defines the state of failure as occurring when the member can no longer serve its structural purpose, whether it be due to excessive cracking or excessive deformation or complete ruin of the member. Such theoretical definitions are difficult to apply since, in a test, it is not easy to verify when a particular state is reached. The measurement of the deformations at the critical section, the position of which is at first unknown, is a delicate operation. The only factor that is readily determinable is the greatest load sustained by the test specimen, but the load causing failure depends on whether the load is applied rapidly or in increments. Gradual loading with considerable periods between each increment gives more consistent results, but tests of long duration are often inconvenient and can only be carried out in especially well-equipped laboratories; interpretation of the results is, however, complicated by the occurrence of creep. These difficulties have led

the Committee to define the state of failure experimentally. The procedure recommended requires the load to be applied in specified increments throughout a period of not less than three hours but in such a manner that the test can be considered as one of short duration; the greatest load sustained is defined as the ultimate load ("charge de rupture"). The primary factors, such as deformation, compressive strain in the concrete and tensile strain in the reinforcement, are reckoned to be taken into account, and on the basis of this hypothesis a method of calculation of the ultimate resistance of members subjected to bending, direct compression, or combined stress is established. The recommendations and methods of testing are given in great detail in a report² published earlier this year.

The second main problem raises the question: What is the strength of concrete? As is well known, cubes, cylinders and prisms of various sizes are used in different countries as standard test pieces and the results obtained from specimens of different shapes differ considerably. Despite much research, a simple relationship between these results has not yet been established because the relationship is affected by numerous factors, the principal being the "strength" of the concrete and, to a less degree but importantly, the fineness of the aggregate. Uniformity of shape and size is aimed at by the pronouncement by the International Association of Testing Materials and Research Laboratories for Materials and Structures (RILEM), that the international standard should be a cylinder 12 in. long and 6 in. in diameter; the Committee concurs with this proposal. According to investigations, particularly those made recently in Norway, friction at the loading surfaces, which increases the apparent crushing strength of concrete, is said to be the primary cause of the varying relationship between the results obtained from cubes and cylinders. A cylinder fails where the frictional effects are least significant, and the distribution of stress is more uniform in a cylinder the height of which is at least twice its diameter. A practical advantage is that cylindrical cores can be readily cut from hardened concrete. Since failure of concrete, whether in compression or tension, is a rending apart of the constituent particles, it is probable that the tensile strength is the basic factor and, if this be so, some form of splitting test may give a truer value of the strength; in such tests it is thought that the shape of the specimen is of little importance. It may be that it is easier to correlate tensile and apparent compressive strengths than it is to correlate the crushing strengths of specimens of various shapes, and therefore some form of tensile test may yet be preferable as an international standard.

If the cylinder test is adopted throughout Europe, there will accrue the advantage that practice in Europe and the U.S.A. is alike, but some complications may be raised for such countries, Great Britain in particular, where hitherto all regulations, codes and general practice are based on the crushing strength of 6-in. cubes. The opinions of engineers in this country would be of interest, and readers are invited to contribute their views on this subject.

(1) "Cement Standards of the World." (Published by Cembureau, Sweden. Distributed in the United Kingdom by Concrete Publications Ltd. Price 25s.; by post 25s. 9d.)

(2) "Preparation of Practical European Standards for the Ultimate Strength Calculation of Reinforced Concrete Structures." European Committee on Concrete Report. By Y. Saillard. "Publications 1960." International Association for Bridge and Structural Engineering. (Published by Verlag Leeman, Zürich. See page 396 of this journal.)

Book Reviews.

"The Design of Cylindrical Shell Roofs."

By J. E. Gibson. (London: E. & F. N. Spon Ltd. Second edition. 1961. Price 52s.)

THE revised edition of this book, the first edition of which appeared with Mr. D. W. Cooper as co-author, contains four new chapters dealing respectively with the use of electronic digital computers for the analysis of shells, reinforced cement-mortar models as a basis of the design of complex shell structures, the design of the frames supporting shell structures, and an account of the practical aspect of shell construction. The photo-elastic investigation of a rigid traverse, which was given in the previous edition, is omitted. The derivations of the formulae used in the book are given in an appendix. The method of presentation is particularly clear and the use of one basic example throughout enables the various stresses occurring in short, intermediate and long shells to be compared. The accuracy of various approximate methods and the advantages obtained by prestressing edge beams are indicated. It is to be regretted that the opportunity was not taken, when preparing this edition, to improve the parts dealing with the design and detailing of the reinforcement in a shell, which are below the standard of the rest of the book.

"Pile Foundations."

By R. D. Chellis. (London: McGraw-Hill Publishing Co., Ltd. Second edition. 1961. Price £6 4s.)

THE second edition of this book, the first of which was published ten years ago, contains much additional matter and has been brought up to date. It covers practically the entire subject of piles and piled foundations and includes a particularly good chapter on the deterioration and preservation of timber piles. The strengthening of soils by compaction, electro-osmosis, freezing and similar methods is described with a useful amount of detail. The subject matter is supported by data and numerous tables, and while some of these are also available in manufacturers' publications, the fact that so much is contained in one volume makes the new edition an essential reference book for designers and contractors dealing with foundations.

British readers may need to remember, or become familiar for the first time, with American terms which differ from those in use in this country; for example, "cushion" in place of "head packing", and "driving cap" instead of "helmet". There are, of course, differences also in practice and in the equipment normally used for particular operations, but this may make the book of more interest as it describes methods which are not well known or little used here. In many books of this type, there are particular sections which even alone would make the book a valuable source of information; the part dealing with diesel hammers is one such section.

No doubt it will not be many years before another edition is required, and when that happens more information could be usefully given on prestressed concrete piles which in recent years have come into general use in the U.S.A.

For those interested in impact formulae, the historical background of some important formulae is largely repeated from the earlier edition and brought up to date by references to the work of Mr. E. A. Smith. There are also useful chapters on pile-loading tests, failures of piled foundations and an appendix giving standard specifications.—D. H. L.

"Festigkeit der Biegedruckzone."

By Gunter Scholz. (Berlin: Wilhelm Ernst & Son. 1960. DM. 10.70.)

THIS publication describes tests of reinforced concrete beams to determine the distribution of stress in the concrete and to establish the magnitude and position of the compressive force for heavy loads and for different qualities of concrete. The main purpose of this publication is a critical appreciation of an article entitled "The distribution of concrete stress in reinforced and prestressed concrete beams when tested to destruction by a pure bending moment", published in the "Magazine of Concrete Research", January 1951. The recommendations for relationship between stress and strain are compared with test results and the discrepancies are discussed. The conclusions, however, are so far not of practical use but are an incentive to further study.

Forces in Three-dimensional Groups of Piles.—I.

By W. E. SCRIVEN, B.Sc. (Eng.).

THE theory in this analysis is based on that proposed by Professor H. M. Westergaard⁽¹⁾ and is applied to three-dimensional groups of piles in general and, in particular, to some common symmetrical groups. The theory can also be applied to groups of columns if the basic assumptions are satisfied. The assumptions made are that all piles are pin-jointed at both ends, and that the pile-cap is rigid and capable of transmitting loads and displacements to the piles without itself being deformed.

General Analysis.

Consider any pile PQ (Fig. 1) with reference to a right-handed set of orthogonal axes OX, OY, OZ such that the co-ordinates of the junction of pile and pile-cap are x, y, z . Due to the external forces P_x, P_y, P_z and moments M_x, M_y, M_z the point x, y, z is displaced by amounts u, v, w in the directions OX, OY, OZ and is rotated through angles α, β, γ in the planes ZOY, XOZ, YOX. All movements and rotations are considered positive if they produce a shortening of the pile.

If l, m, n are the directional cosines of the pile, the total shortening due to translational movement is s_1 , such that

$$s_1 = u.l + v.m + w.n. \quad (1)$$

If point C (x_0, y_0, z_0) is the centre of rotation of the group of piles, consider first




Fig. 1.

(1) H. M. WESTERGAARD. "The Resistance of a Group of Piles." Journal of Western Soc. of Eng., 1917.

the rotation in the ZOY plane (Fig. 1). The pile PQ is moved from P to P_1 by the rotation α . From the geometry of the figure, $PP_1 = \alpha \cdot C_1P$;

$$\widehat{APP}_1 = \frac{\pi}{2} - \frac{\alpha}{2} - (\pi - \mu) = \left(\mu - \frac{\alpha}{2}\right) - \frac{\pi}{2};$$

$$\cos \widehat{APP}_1 = \sin \left(\mu - \frac{\alpha}{2}\right) = \sin \mu \text{ nearly; and}$$

$$\sin \widehat{APP}_1 = \cos \left(\mu - \frac{\alpha}{2}\right) = \cos \mu \text{ nearly.}$$

But $\cos \mu = -\frac{(y-y_0)}{C_1P}$ and $\sin \mu = \frac{z_0-z}{C_1P}$; hence

$$AP = PP_1 \cos \widehat{APP}_1 = -\alpha(z-z_0) \text{ and } AP_1 = PP_1 \sin \widehat{APP}_1 = -\alpha(y-y_0).$$

The co-ordinates of P_1 are therefore $[x, y - \alpha(z - z_0), z - \alpha(y - y_0)]$, and the co-ordinates of the remote end Q of the pile are $[x + Ll, y + Lm, z - Ln]$, in which L is the length of the pile. Hence the shortening of the pile due to the rotation α is

$$s_\alpha = L - \{[x + Ll - x]^2 + [y + Lm - y + \alpha(z - z_0)]^2 + [z - Ln - z + \alpha(y - y_0)]^2\}^{\frac{1}{2}} \\ = L - \{L^2 + 2\alpha L[m(z - z_0) - n(y - y_0)]\}^{\frac{1}{2}}, \text{ ignoring terms in } \alpha^2.$$

Expanding by the binomial theorem and ignoring second and subsequent terms,

$$s_\alpha = \alpha[n(y - y_0) - m(z - z_0)] = \alpha R,$$

and similarly

$$s_\beta = \beta[l(z - z_0) - n(x - x_0)] = \beta S,$$

and

$$s_\gamma = \gamma[m(x - x_0) - l(y - y_0)] = \gamma T,$$

in which the symbols R, S, T represent the expressions in square brackets. The total shortening in any pile is then

$$s_T = s_1 + s_\alpha + s_\beta + s_\gamma = u.l + v.m + w.n + \alpha.R + \beta.S + \gamma.T \quad (2)$$

If the force in any pile is F , then

$$F = \frac{AE}{L} \times s_T = Q.s_T \quad (3)$$

in which $Q = \frac{AE}{L}$ and A is the cross-sectional area, E the elastic modulus, and L the length of the pile. [This symbol A is not the same as that in equation (4).]

Clearly, if the centre of rotation can be found, the displacements and rotations can be calculated and a solution obtained. The centre of rotation must be such that the least moment of resistance of the group of piles is obtained at that point. Hence $\Sigma Q\phi^2$ must be a minimum, in which ϕ is the least perpendicular distance of the centre-line of the pile from point C (x_0, y_0, z_0) .

If L', M', N' are the directional cosines of the line joining P (x, y, z) to C (x_0, y_0, z_0) (Fig. 2), then

$$L', M', N' = \frac{(x - x_0), (y - y_0), (z - z_0)}{\sqrt{(x - x_0)^2 + (y - y_0)^2 + (z - z_0)^2}}$$




Fig. 2.




Fig. 3.

and if θ is the angle between the centre-line of the pile and the line PC,

$$p = PC \sin \theta$$

$$= [\sqrt{(x - x_0)^2 + (y - y_0)^2 + (z - z_0)^2}] [\sqrt{\Sigma(Mn - Nm)^2}]$$

$$= \sqrt{\Sigma[n(y - y_0) - m(z - z_0)]^2}$$

$$= [R^2 + S^2 + T^2]^{\frac{1}{2}},$$

in which Σ denotes the sum of the three cyclic terms.

Now since $\Sigma Q p^2$ is a minimum $\Sigma Q p \frac{\partial p}{\partial x_0} = \Sigma Q p \frac{\partial p}{\partial y_0} = \Sigma Q p \frac{\partial p}{\partial z_0} = 0$.

Hence if $p \neq 0$, $\Sigma Q(nS - mT) = \Sigma Q(lT - nR) = \Sigma Q(mR - lS) = 0$.

The solutions of these equations are

$$\left. \begin{aligned} x_0 &= + \frac{1}{A_1} \begin{vmatrix} -\Sigma Qlm & -\Sigma Qln & \Sigma QA \\ \Sigma Q(l^2 + n^2) & -\Sigma Qmn & \Sigma QB \\ -\Sigma Qmn & \Sigma Q(l^2 + m^2) & \Sigma QC \end{vmatrix} \\ y_0 &= - \frac{1}{A_1} \begin{vmatrix} \Sigma Q(m^2 + n^2) & -\Sigma Qln & \Sigma QA \\ -\Sigma Qlm & -\Sigma Qmn & \Sigma QB \\ -\Sigma Qln & \Sigma Q(l^2 + m^2) & \Sigma QC \end{vmatrix} \\ z_0 &= + \frac{1}{A_1} \begin{vmatrix} \Sigma Q(m^2 + n^2) & -\Sigma Qlm & \Sigma QA \\ -\Sigma Qlm & \Sigma Q(l^2 + n^2) & \Sigma QB \\ -\Sigma Qln & -\Sigma Qmn & \Sigma QC \end{vmatrix} \end{aligned} \right\} \quad (4)$$

$$\text{in which } A_1 = - \begin{vmatrix} \Sigma Q(m^2 + n^2) & -\Sigma Qlm & -\Sigma Qln \\ -\Sigma Qlm & \Sigma Q(l^2 + n^2) & -\Sigma Qmn \\ -\Sigma Qln & -\Sigma Qmn & \Sigma Q(l^2 + m^2) \end{vmatrix}$$

and

$$A = -(m^2 + n^2)x + lmy + lnz;$$

$$B = lmx - (l^2 + n^2)y + mnz;$$

$$C = lnx + mny - (l^2 + m^2)z.$$

$$\left. \begin{aligned} \text{For equilibrium } P_x &= \Sigma F_l \\ P_y &= \Sigma F_m \\ P_z &= \Sigma F_n \\ M_x &= \Sigma F[n(y - y_0) - m(z - z_0)] = \Sigma F R \\ M_y &= \Sigma F[l(z - z_0) - n(x - x_0)] = \Sigma F S \\ M_z &= \Sigma F[m(x - x_0) - l(y - y_0)] = \Sigma F T \end{aligned} \right\} \quad (5)$$

If these conditions are substituted in formulæ (2) and (3),

$$\left. \begin{aligned} P_x &= \Sigma Q \cdot l(ul + vm + wn + \alpha R + \beta S + \gamma T) \\ M_x &= \Sigma Q \cdot R(ul + vm + wn + \alpha R + \beta S + \gamma T) \end{aligned} \right\} \quad (6)$$

and similarly for P_y , P_z and M_y , M_z .

These formulæ yield the required values of u , v , w , α , β and γ and the force in any pile is then given by

$$F_i = Q_i (ul_i + vm_i + wn_i + \alpha R_i + \beta S_i + \gamma T_i) \quad (7)$$

in which the suffix i denotes the values for the particular pile.

MOMENT NOTATION.—External non-axial loads on the pile group cause moments, the magnitude and direction of which can be expressed in terms of the last three of formulæ (5). Suppose, for instance, that in any group a force P_y acts at a distance z from, and parallel to, the OY axis, and a force P_z acts at a distance y from, and parallel to, the OZ axis; the applied moment, from (5), is then $M_x = P_z(y - y_0) - P_y(z - z_0)$. The sign convention is in accordance with the selected set of axes, a positive value of M_x tending to rotate the Y-axis clockwise about the X-axis into the Z-axis (Fig. 4).

REDUCTION TO TWO-DIMENSIONAL SYSTEM.—Before considering particular three-dimensional cases it is of interest to investigate the reduction of the general solution to a two-dimensional case where all pile-heads are at the same level. The notation is shown in Fig. 3, and the following abbreviations are used.

$$\begin{aligned} \Sigma_1 &= \Sigma Q \cos^2 \theta; \Sigma_2 = \Sigma Q \sin \theta \cos \theta; \Sigma_3 = \Sigma Q x \cos^2 \theta; \\ \Sigma_4 &= \Sigma Q x \sin \theta \cos \theta; \Sigma_5 = \Sigma Q \sin^2 \theta; \Sigma_6 = \Sigma Q X^2 \cos^2 \theta, \end{aligned}$$

in which $X = (x - x_0) + z_0 \tan \theta$.

Now $l = \cos(\pi/2 + \theta) = -\sin \theta$, $m = 0$, and $n = -\cos \theta$;

$$P_x = -H, \quad P_y = 0, \quad P_z = -W,$$

and $M_y = P_z(f - z_0) - P_x(e - x_0) = W(e - x_0) + H(z_0 - f)$.




Fig. 4.

Therefore
$$A_1 = - \begin{vmatrix} \Sigma Q \cos^2 \theta & 0 & \Sigma Q \sin \theta \cos \theta \\ 0 & 1 & 0 \\ \Sigma Q \sin \theta \cos \theta & 0 & \Sigma Q \sin^2 \theta \end{vmatrix}$$

$$= - \Sigma Q \cos^2 \theta \Sigma Q \sin^2 \theta + (\Sigma Q \sin \theta \cos \theta)^2$$

$$= - \Sigma_1 \Sigma_3 + (\Sigma_2)^2 = -G.$$

From formula (4)
$$z_0 = \frac{1}{A_1} \begin{vmatrix} \Sigma Q \cos^2 \theta & 0 & -\Sigma Q x \cos^2 \theta \\ 0 & 1 & 0 \\ -\Sigma Q \sin \theta \cos \theta & 0 & \Sigma Q x \sin \theta \cos \theta \end{vmatrix}$$

$$= \frac{1}{A_1} \left\{ \Sigma Q \cos^2 \theta \Sigma Q x \sin \theta \cos \theta - \Sigma Q \sin \theta \cos \theta \Sigma Q x \cos^2 \theta \right\}$$

$$= \frac{1}{A_1} (\Sigma_1 \Sigma_4 - \Sigma_2 \Sigma_3) = \frac{\Sigma_2 \Sigma_3 - \Sigma_1 \Sigma_4}{G}.$$

Similarly from formula (4),
$$x_0 = \frac{\Sigma_2 \Sigma_3 - \Sigma_1 \Sigma_4}{G}.$$

Also $R = 0$, $S = z_0 \sin \theta + (x - x_0) \cos \theta = X \cos \theta$, and $T = 0$; formulæ (6) can therefore be written in the form

$$\begin{aligned} u \Sigma Q \sin^2 \theta + w \Sigma Q \sin \theta \cos \theta - \beta \Sigma Q X \sin \theta \cos \theta + H &= 0 \\ u \Sigma Q \sin \theta \cos \theta + w \Sigma Q \cos^2 \theta - \beta \Sigma Q X \cos^2 \theta + W &= 0 \\ -u \Sigma Q X \sin \theta \cos \theta + w \Sigma Q X \cos^2 \theta + \beta \Sigma Q X^2 \cos^2 \theta - M &= 0. \end{aligned}$$

But $X \sin \theta \cos \theta = z_0 \sin^2 \theta + (x - x_0) \sin \theta \cos \theta = z_0 \Sigma_3 + \Sigma_4 - x_0 \Sigma_2 = 0$.

Similarly $\Sigma Q X \cos^2 \theta = z_0 \Sigma_2 + \Sigma_3 - x_0 \Sigma_1 = 0$ and the foregoing formulæ reduce to

$$\begin{aligned} u \Sigma_3 + w \Sigma_2 + H &= 0 \\ u \Sigma_2 + w \Sigma_1 + W &= 0 \\ \beta \Sigma_3 - M &= 0. \end{aligned}$$

From these, $u = \frac{W \Sigma_2 - H \Sigma_1}{-G}$; $w = \frac{W \Sigma_3 - H \Sigma_2}{-G}$; and $\beta = \frac{M}{\Sigma_3}$, and, substituting in formula (7),

$$\begin{aligned} F_1 &= \{u \sin \theta_1 - w \cos \theta_1 + \beta [z_0 \sin \theta_1 + (x_1 - x_0) \cos \theta_1]\} Q_1 \\ &= \cos \theta_1 \left\{ \frac{H \Sigma_1 - W \Sigma_2}{G} \tan \theta_1 - \frac{H \Sigma_2 - W \Sigma_3}{G} + \frac{M \cdot X_1}{\Sigma_3} \right\} Q_1 \\ &= \cos \theta_1 \left\{ W \left[\frac{\Sigma_3 - \Sigma_2 \tan \theta_1}{G} \right] + H \left[\frac{\Sigma_1 \tan \theta_1 - \Sigma_2}{G} \right] + \frac{M \cdot X_1}{\Sigma_3} \right\} Q_1. \end{aligned}$$

From this result the force in any pile may be determined.

Circular Groups.

Consider the case in which the piles are grouped symmetrically about a circle of radius a in the plane XOY; that is, for all piles $z = 0$. The co-ordinate system is illustrated in Fig. 5, from which

$$x = a \sin \theta; \quad y = a \cos \theta \quad . \quad . \quad . \quad . \quad (8)$$




Fig. 5.

NOTE.—In the analysis on pages 376 to 378, the symbol μ represents angle η in this diagram.

The directional cosines of PQ are then

$$l = \sin \mu \cdot \sin (\theta + \phi); \quad m = \sin \mu \cdot \cos (\theta + \phi); \quad n = -\cos \mu \quad (9)$$

If all piles have equal values of Q , then by symmetry

$$\Sigma Qmn = \Sigma Qln = \Sigma Qlm = \Sigma Qmnx = \Sigma Qlny = \Sigma Qlmx = \Sigma Ql^2x = \Sigma Ql^2y = \Sigma Qlm_y = \Sigma Qm^2x = \Sigma Qm^2y = \Sigma Qn^2x = \Sigma Qn^2y = 0.$$

Hence

$$A = B = 0 \quad \text{and} \quad C = \Sigma Qlnx + \Sigma Qmny.$$

Also

$$A_1 = -\Sigma Q(l^2 + m^2) \cdot \Sigma Q(m^2 + n^2) \cdot \Sigma Q(l^2 + n^2),$$

$$x_0 = y_0 = 0, \quad \text{and} \quad z_0 = \frac{1}{A_1} \{ \Sigma Q(m^2 + n^2) \cdot \Sigma Q(l^2 + n^2) \cdot \Sigma QC \}$$

$$= \frac{1}{\Sigma Q(l^2 + m^2)} (\Sigma Qlnx + \Sigma Qmny).$$

Substituting from equation (9),

$$z_0 = \frac{1}{\sin^2 \mu \Sigma Q} \times a \sin \mu \cos \mu \{ \Sigma Q \sin (\theta + \phi) \sin \theta + \Sigma Q \cos (\theta + \phi) \cos \theta \}$$

$$= \frac{a \sin \mu \cos \mu \cos \phi}{\sin^2 \mu} = a \cot \mu \cos \phi \quad (10)$$

Substituting in equation (5),

$$R = n \cdot y + m \cdot z_0; \quad S = -l \cdot z_0 - n \cdot x; \quad T = m \cdot x - l \cdot y,$$

and since $\Sigma Qn^2x \cdot y = \Sigma Qmnxy = \Sigma Qlny^2 = 0$, and

$$\Sigma QR^2 = \Sigma Qn^2y^2 + z_0^2 \Sigma Q \cdot m^2 + 2z_0 \Sigma Qmny;$$

$$\Sigma QS^2 = z_0^2 \Sigma Ql^2 + \Sigma Qn^2x^2 + 2z_0 \Sigma Qln \cdot x;$$

$$\Sigma QT^2 = \Sigma Qm^2x^2 + \Sigma Ql^2y^2; \quad \text{it follows that}$$

$$\Sigma QmR = \Sigma Qmny + z_0 \Sigma Qm^2; \quad \Sigma QlS = -z_0 \Sigma Ql^2 - \Sigma Qlnx;$$

$$\Sigma QlR = \Sigma QnR = \Sigma QmS = \Sigma QnS = \Sigma QlT = \Sigma QRS = \Sigma QmT = \Sigma QTR = \Sigma QnT = \Sigma QTS = 0.$$

Assume now that all piles have the same angles μ and ϕ . Let there be N piles,

spaced at angular intervals of δ ; then $\delta = \frac{2\pi}{N}$. The summations required for the solution are

$$\begin{aligned}\Sigma Ql^2 &= \sin^2 \mu \Sigma Q \sin^2 (\theta + \phi); \quad \Sigma Qm^2 = \sin^2 \mu \cdot \Sigma Q \cos^2 (\theta + \phi); \\ \Sigma Qn^2 &= \cos^2 \mu \Sigma Q; \quad \Sigma Qnlx = -a \sin \mu \cos \mu \cdot \Sigma Q \sin (\theta + \phi) \sin \theta; \\ \Sigma Qmny &= -a \sin \mu \cos \mu \cdot \Sigma Q \cos (\theta + \phi) \cos \theta; \\ \Sigma Ql^2x^2 &= a^2 \sin^2 \mu \cdot \Sigma Q \sin^2 (\theta + \phi) \sin^2 \theta; \\ \Sigma Qm^2x^2 &= a^2 \sin^2 \mu \cdot \Sigma Q \cos^2 (\theta + \phi) \sin^2 \theta; \\ \Sigma Qn^2x^2 &= a^2 \cos^2 \mu \cdot \Sigma Q \sin^2 \theta; \quad \Sigma Ql^2y^2 = a^2 \sin^2 \mu \cdot \Sigma Q \sin^2 (\theta + \phi) \cos^2 \theta; \\ \Sigma Qn^2y^2 &= a^2 \cos^2 \mu \cdot \Sigma Q \cos^2 \theta.\end{aligned}$$

It can be shown that

$$\begin{aligned}\sin \theta_1 + \sin (\theta_1 + \delta) + \sin (\theta_1 + 2\delta) + \dots + \sin (\theta_1 + [N-1]\delta) \\ = \frac{\sin \left[\theta_1 + \left(\frac{N-1}{2} \right) \delta \right] \sin \frac{N\delta}{2}}{\sin \frac{\delta}{2}}\end{aligned}$$

$$\begin{aligned}\text{and } \cos \theta_1 + \cos (\theta_1 + \delta) + \cos (\theta_1 + 2\delta) + \dots + \cos (\theta_1 + [N-1]\delta) \\ = \frac{\cos \left[\theta_1 + \left(\frac{N-1}{2} \right) \delta \right] \sin \frac{N\delta}{2}}{\sin \frac{\delta}{2}}.\end{aligned}$$

$$\text{Let } \theta_1 = \frac{\delta}{2} = \frac{\pi}{N}; \text{ hence } \Sigma \sin \theta = \sin^2 \pi \operatorname{cosec} \frac{\pi}{N} = \Sigma \cos \theta$$

$$= \frac{1}{2} \sin 2\pi \operatorname{cosec} \frac{\pi}{N} = 0.$$

$$\text{Similarly } \Sigma \sin 2\theta = \Sigma \cos 2\theta = \Sigma \sin 4\theta = \Sigma \cos 4\theta = 0.$$

Substituting these identities in the summations assuming Q to be constant,

$$\Sigma Ql^2 = \Sigma Qm^2 = \frac{N}{2} \sin^2 \mu; \quad \Sigma Qnlx = \Sigma Qmny = -a \frac{N}{2} \sin \mu \cos \mu \cos \phi;$$

$$\Sigma Qn^2 = N \cos^2 \mu; \quad \Sigma Ql^2x^2 = \frac{a^2 N}{4} \sin^2 \mu (1 + 2 \cos \phi);$$

$$\Sigma Qm^2x^2 = \Sigma Ql^2y^2 = \frac{a^2 N}{4} \sin^2 \mu (1 - 2 \cos \phi);$$

$$\Sigma Qn^2x^2 = \Sigma Qn^2y^2 = \frac{a^2 N}{2} \cos^2 \mu; \quad \Sigma QmR = \Sigma QlS = 0;$$

$$\Sigma QR^2 = \Sigma QS^2 = \frac{a^2 N}{2} \cos^2 \mu \sin^2 \phi; \quad \Sigma QT^2 = \frac{a^2 N}{2} \sin^2 \mu (1 - 2 \cos \phi).$$

Substituting these results into equation (6),

$$\left. \begin{aligned}u &= \frac{2P_x}{N \sin^2 \mu}; \quad v = \frac{2P_y}{N \sin^2 \mu}; \quad w = \frac{P_z}{N \cos^2 \mu}; \quad \alpha = \frac{2M_x}{a^2 N \cos^2 \mu \sin^2 \phi}; \\ \beta &= \frac{2My}{a^2 N \cos^2 \mu \sin^2 \phi}; \quad \gamma = \frac{2M_z}{a^2 N \sin^2 \mu (1 - 2 \cos \phi)}.\end{aligned} \right\} \quad (11)$$

The force in any pile is found by substitution in equation (7), which can then be reduced to give

$$F_\theta = \frac{2P_v \sin(\theta + \phi)}{N \sin \mu} + \frac{2P_v \cos(\theta + \phi)}{N \sin \mu} - \frac{P_s}{N \cos \mu} - \frac{2M_s \sin(\theta + \phi)}{aN \cos \mu \sin \phi} - \frac{2M_v \cos(\theta + \phi)}{aN \cos \mu \sin \phi} + \frac{2M_s \cos \phi}{aN \sin \mu(1 - 2 \cos \phi)} \quad (12)$$

Equation (12) enables any group of piles to be solved if all the piles have equal values of a , μ and ϕ , and there is only one pile at each node point. The problem of several piles at each node, with different values of μ and ϕ , is now considered, but in order to reduce the amount of algebra involved only the moments and forces acting in one plane (ZOY) are considered. For this case $P_s = M_v = M_s = 0$, and

$$F_\theta = P_v \frac{2 \cos(\theta + \phi)}{N \sin \mu} - P_v \frac{1}{N \cos \mu} - M_s \frac{2 \sin(\theta + \phi)}{aN \cos \mu \sin \phi} \quad (13)$$

If the values of a , μ and ϕ are different for each group, then

$$v = \frac{2P_v}{\Sigma N \sin^2 \mu}; \quad w = \frac{P_s}{\Sigma N \cos^2 \mu}; \quad \alpha = \frac{2M_s}{\Sigma a^2 N \cos^2 \mu \sin^2 \phi};$$

and

$$z_0 = \frac{\Sigma a N \sin \mu \cos \mu \cos \phi}{\Sigma N \sin^2 \mu} \quad (14)$$

Hence

$$F_{a_1, \phi_1} = v \{ \sin \mu_1 \cos(\theta + \phi_1) \} - w \cos \mu_1 - \alpha \{ a_1 \sin(\theta + \phi_1) \sin \phi_1 \cos \mu_1 \} \quad (15)$$

The application of the foregoing expressions is illustrated in three examples to be given in a continuation of this article.

(To be continued.)

Bulletins Received.

- "The Ultimate Load of Simply Supported Skew Slab Bridges." By C. A. Granholm and R. E. Rowe. (London: Cement & Concrete Association. 1961.)
- "Tests on a Particular Design of Reinforced Concrete Rocker Bearing for Motorway Bridges." By G. D. Base. (London: Cement & Concrete Association. 1961.)
- "Lajes Continuas de Pontes." By T. van Langendonck. (Rio De Janeiro: 1961. Brazilian Portland Cement Association. In Portuguese. No price stated.)
- "Beiträge zu ausgewählten Problemen des Massivbaues." By F. Lardy. (Zürich: Verlag Leemann. 1961. In German. Price 15 Swiss francs.)
- "Theory of Non-homogeneous Anisotropic Elastic Shells Subjected to Arbitrary Temperature Distribution." By R. E. Miller. (University of Illinois. 1961. Engineering Experiment Station Bulletin No. 458. Price 1 dollar.)
- "Theoretical and Experimental Analyses of Members Made of Materials that Creep." By O. M. Sidebottom, G. A. Costello, and S. Dharmarajan. (University of Illinois. 1961. Engineering Experiment Station Bulletin No. 460. Price 1 dollar.)
- "Shear Strength of Restrained Concrete Beams Without Web Reinforcement." By J. E. Bower and I. M. Viest. (Chicago: The Portland Cement Association. 1961. The Reinforced Concrete Research Council Bulletin No. 14. No price stated.)
- "High-Strength Deformed Steel Bars for Concrete Reinforcement." By S. A. Guralnick. (Chicago: The Portland Cement Association. 1961. The Reinforced Concrete Research Council Bulletin No. 15. No price stated.)
- "Concrete Pavement Construction." (Washington, D.C.: Highway Research Board. 1960. Bulletin 265. Price 1.40 dollars.)
- "Flexible Pavement Design Studies—1960." (Washington, D.C.: Highway Research Board. 1960. Bulletin 269. Price 1.60 dollars.)
- "Asphalt Characteristics and Asphaltic Concrete Construction." (Washington, D.C.: Highway Research Board. 1960. Bulletin 270. Price 1.40 dollars.)



FIG. 1.

A Bridge in Northern Ireland.

By JOHN FABER, B.Sc., M.I.C.E., M.I.Struct.E.

A REINFORCED concrete bridge (Fig. 1) 320 ft. long was recently constructed, for the British Portland Cement Manufacturers Ltd., near the quarry serving the cement works at Magheramorne, near Larne, Northern Ireland. To win chalk for the manufacture of cement, it is necessary to dispose of a basalt overburden at the rate of 2,000,000 tons per year. The basalt is being tipped into Larne Lough with a view that eventually a causeway may be formed across the Lough to Island Magee. From the quarry on the west side, the new concrete bridge gives access directly over a public main road and the Belfast-Larne railway to Larne Lough on the east side.

Design Requirements.

For the past fifteen years, the road and railway were crossed by dumpers of medium size using a temporary steel bridge, so that a considerable tip of basalt has already been formed in the Lough. Therefore the eastern end of the new bridge had to be founded on the tip. Another requirement was that the line of the bridge should be arranged to suit a possible future belt-conveyor to be used as an alternative method of transporting the basalt. These requirements, together with the disposition of the three railway tracks and the improved line for the main road, led to siting the bridge on a skew and providing three main spans each 81 ft. long.

The large dumpers, which the bridge is designed to carry, are 32½ ft. long and 12½ ft. wide, and weigh 70 tons when fully laden. In case a dumper breaks down on the bridge, another dumper would go on the bridge to push it off and thus two machines can be on a span at the same

time. Other loads and forces have been provided for as follows. Due to the surface of the carriageway being uneven because of spillings from the vehicles, a vertical impact effect of 30 per cent. of the weight of one laden vehicle is assumed. Due to the very efficient braking, a longitudinal thrust equal to the laden weight of the vehicle is taken into account. Due to lateral sway, the wheels on one side are assumed to carry five-eighths of the total load of the vehicle.

The requirement that boulders spilled from the dumpers should be prevented from falling on to the railway or road has led to the adoption of resilient walkways on both sides of the bridge, with parapets of substantial construction though not of unusual height. These measures give the bridge a sober aesthetic appearance, whereas higher parapets on a narrower deck would have looked curious and would have cost more.

Alternative Designs of the Deck.

Alternative designs of the deck were considered (Fig. 3). The first scheme was to provide precast prestressed trough-shaped beams with post-tensioned steel, there being four beams side by side on each span. The beams were to have been precast on the existing tip in the Lough, and launched by suspension from a steel lattice girder so that each beam would be suspended at two points near its ends. When the beams had been placed for the easternmost span, the deck slab for that span would be cast *in situ*, and would act as the compression flange when the bridge was in service. The precast beams for the next span would then be launched over the first span, and so on.

While the preliminary design was

The force in any pile is found by substitution in equation (7), which can then be reduced to give

$$F_{\theta} = \frac{2P_v \sin(\theta + \phi)}{N \sin \mu} + \frac{2P_v \cos(\theta + \phi)}{N \sin \mu} - \frac{P_z}{N \cos \mu} - \frac{2M_s \sin(\theta + \phi)}{aN \cos \mu \sin \phi} \\ - \frac{2M_s \cos(\theta + \phi)}{aN \cos \mu \sin \phi} + \frac{2M_s \cos \phi}{aN \sin \mu (1 - 2 \cos \phi)} \quad (12)$$

Equation (12) enables any group of piles to be solved if all the piles have equal values of a , μ and ϕ , and there is only one pile at each node point. The problem of several piles at each node, with different values of μ and ϕ , is now considered, but in order to reduce the amount of algebra involved only the moments and forces acting in one plane (ZOY) are considered. For this case $P_x = M_x = M_z = 0$, and

$$F_{\theta} = P_v \frac{2 \cos(\theta + \phi)}{N \sin \mu} - P_z \frac{1}{N \cos \mu} - M_s \frac{2 \sin(\theta + \phi)}{aN \cos \mu \sin \phi} \quad (13)$$

If the values of a , μ and ϕ are different for each group, then

$$v = \frac{2P_v}{\Sigma N \sin^2 \mu}; \quad w = \frac{P_z}{\Sigma N \cos^2 \mu}; \quad \alpha = \frac{2M_s}{\Sigma a^2 N \cos^2 \mu \sin^2 \phi}; \\ \text{and} \quad z_0 = \frac{\Sigma a N \sin \mu \cos \mu \cos \phi}{\Sigma N \sin^2 \mu} \quad (14)$$

Hence

$$F_{\theta, \mu, \phi}^p = v \{\sin \mu_1 \cos(\theta + \phi_1)\} - w \cos \mu_1 - \alpha \{a_1 \sin(\theta + \phi_1) \sin \phi_1 \cos \mu_1\} \quad (15)$$

The application of the foregoing expressions is illustrated in three examples to be given in a continuation of this article.

(To be continued.)

Bulletins Received.

- "The Ultimate Load of Simply Supported Skew Slab Bridges." By C. A. Granholm and R. E. Rowe. (London: Cement & Concrete Association. 1961.)
- "Tests on a Particular Design of Reinforced Concrete Rocker Bearing for Motorway Bridges." By G. D. Base. (London: Cement & Concrete Association. 1961.)
- "Lajes Continuas de Pontes." By T. van Langendonck. (Rio De Janeiro: 1961. Brazilian Portland Cement Association. In Portuguese. No price stated.)
- "Beiträge zu ausgewählten Problemen des Massivbaues." By P. Lardy. (Zürich: Verlag Leemann. 1961. In German. Price 15 Swiss francs.)
- "Theory of Non-homogeneous Anisotropic Elastic Shells Subjected to Arbitrary Temperature Distribution." By R. E. Miller. (University of Illinois. 1961. Engineering Experiment Station Bulletin No. 458. Price 1 dollar.)
- "Theoretical and Experimental Analyses of Members Made of Material that Creep." By O. M. Sidebottom, G. A. Costello, and S. Dharmarajan. (University of Illinois. 1961. Engineering Experiment Station Bulletin No. 460. Price 1 dollar.)
- "Shear Strength of Restrained Concrete Beams Without Web Reinforcement." By J. E. Bower and I. M. Viest. (Chicago: The Portland Cement Association. 1961. The Reinforced Concrete Research Council Bulletin No. 14. No price stated.)
- "High-Strength Deformed Steel Bars for Concrete Reinforcement." By S. A. Guralnick. (Chicago: The Portland Cement Association. 1961. The Reinforced Concrete Research Council Bulletin No. 15. No price stated.)
- "Concrete Pavement Construction." (Washington, D.C.: Highway Research Board. 1960. Bulletin 265. Price 1.40 dollars.)
- "Flexible Pavement Design Studies—1960." (Washington, D.C.: Highway Research Board. 1960. Bulletin 269. Price 1.60 dollars.)
- "Asphalt Characteristics and Asphaltic Concrete Construction." (Washington, D.C.: Highway Research Board. 1960. Bulletin 270. Price 1.40 dollars.)



FIG. 1.

A Bridge in Northern Ireland.

By JOHN FABER, B.Sc., M.I.C.E., M.I.Struct.E.

A REINFORCED concrete bridge (Fig. 1) 320 ft. long was recently constructed, for the British Portland Cement Manufacturers Ltd., near the quarry serving the cement works at Magheramorne, near Larne, Northern Ireland. To win chalk for the manufacture of cement, it is necessary to dispose of a basalt overburden at the rate of 2,000,000 tons per year. The basalt is being tipped into Larne Lough with a view that eventually a causeway may be formed across the Lough to Island Magee. From the quarry on the west side, the new concrete bridge gives access directly over a public main road and the Belfast-Larne railway to Larne Lough on the east side.

Design Requirements.

For the past fifteen years, the road and railway were crossed by dumpers of medium size using a temporary steel bridge, so that a considerable tip of basalt has already been formed in the Lough. Therefore the eastern end of the new bridge had to be founded on the tip. Another requirement was that the line of the bridge should be arranged to suit a possible future belt-conveyor to be used as an alternative method of transporting the basalt. These requirements, together with the disposition of the three railway tracks and the improved line for the main road, led to siting the bridge on a skew and providing three main spans each 81 ft. long.

The large dumpers, which the bridge is designed to carry, are 32½ ft. long and 12½ ft. wide, and weigh 70 tons when fully laden. In case a dumper breaks down on the bridge, another dumper would go on the bridge to push it off and thus two machines can be on a span at the same


time. Other loads and forces have been provided for as follows. Due to the surface of the carriageway being uneven because of spillings from the vehicles, a vertical impact effect of 50 per cent. of the weight of one laden vehicle is assumed. Due to the very efficient braking, a longitudinal thrust equal to the laden weight of the vehicle is taken into account. Due to lateral sway, the wheels on one side are assumed to carry five-eighths of the total load of the vehicle.

The requirement that boulders spilled from the dumpers should be prevented from falling on to the railway or road has led to the adoption of resilient walkways on both sides of the bridge, with parapets of substantial construction though not of unusual height. These measures give the bridge a sober aesthetic appearance, whereas higher parapets on a narrower deck would have looked curious and would have cost more.

Alternative Designs of the Deck.

Alternative designs of the deck were considered (Fig. 3). The first scheme was to provide precast prestressed trough-shaped beams with post-tensioned steel, there being four beams side by side on each span. The beams were to have been precast on the existing tip in the Lough, and launched by suspension from a steel lattice girder so that each beam would be suspended at two points near its ends. When the beams had been placed for the easternmost span, the deck slab for that span would be cast *in situ*, and would act as the compression flange when the bridge was in service. The precast beams for the next span would then be launched over the first span, and so on.

While the preliminary design was



being prepared, the ground investigations showed that the so-called basalt tip was so interspersed with clay filling, which was insufficiently consolidated, that no horizontal thrust could be resisted at the eastern end of the bridge; also the provision of adequate vertical support would most likely be difficult. The western abutment, however, would be on hard chalk, and it was decided therefore to anchor all the horizontal thrust back to this end. Precasting and launching from the western end would not have been convenient due to restrictions of the site. Also, the provision of an anchorage at one end only would mean building the bridge in one length without intermediate expansion joints; the great variation in length this method would cause under the effects of temperature, creep, shrinking and braking forces did not suit the scheme with prestressed precast members. This scheme was therefore abandoned.

A second design was therefore developed, and included six reinforced concrete beam-ribs cast insitu on a continuous bird-cage scaffolding. By providing slightly longer piles under the intermediate piers, and by inclining the piles at 1 in 10, it was thought that the settlement would be small enough for the bridge to be designed as a fully continuous structure. (In the precast scheme the beams would have acted as freely-supported members, at least under the influence of all dead loads.) The cost of the scaffolding was found to be less than the combined cost of launching the precast beams combined with the staging subsequently required for the deck slab. The merit of full continuity was that there was an overall saving in cost of the cast-insitu bridge compared with the precast scheme. Furthermore, the reinforced concrete structure as adopted is probably better suited than the prestressed concrete scheme to resist the heavy impact forces.

The Beams.

The dimensions of the beam-ribs were considered in conjunction with the contractor with a view to repetitive use of the shuttering, and to give sufficient space between the ribs for ease of subsequent removal (Fig. 2). The normal objection to a cast-insitu bridge is the cost of providing the support for one and a half spans simultaneously necessary to avoid the

development of deflections and bending moments contrary to the intentions of a fully continuous design; but, by the use of a highly repetitive system of shuttering on the continuous bird-cage scaffolding, this objection does not apply.

The spacing of the beam-ribs and location of transverse diaphragms were such that wherever a vehicle might be on the width of the deck, its weight would be shared by at least five of the six ribs provided. The dimensions of the ribs and the spacing of the reinforcement were arranged to facilitate the use of immersion vibrators for the whole of the work. Prior to construction, the contractor made up a dummy length of beam-rib, 5 ft. long, to determine the effect of the vibrators in the actual cross-section with concrete containing angular crushed basalt which is the only aggregate available in the district.

Foundations.

Ground investigation showed that the west abutment would be on a sloping face of hard chalk. However, it was not discovered until later that part of this chalk had been quarried to a depth of at least 50 ft. (and probably more), and this area of the quarry working had been filled in subsequently with softer material. This necessitated building up the abutment from new ledges cut into the quarry face, a feature which caused some delay but which greatly enhanced the effectiveness of the abutment as an anchorage. The projecting keys at the lower part of the abutment were reinforced with rails which projected into the walls of the hollow-box structure forming the abutment (Fig. 2).

The intermediate piers are founded on a variety of faulted strata, and piled foundations are provided. The piles are of the bored type owing to the inaccessibility of the site and the close proximity of the railway tracks. Clearly a filling of mud had been deposited at the time the railway was constructed, and in boring for the piles it was wished that the engineers who had placed this filling had first removed the wrecks of timber ships lying on the old shore of the Lough. A number of piles were concreted with the boreholes partly filled with water, but two of these piles were tested and proved satisfactory. In service the piled foundations have not moved a measurable amount. At the easternmost pier it was expected

that the basalt tip in the Lough would have squeezed downwards and sideways into the mud, and subsequently this was found to be so. This necessitated excavating to a depth of about 6 ft. immediately adjacent to the railway line before boring for the piles could be started.

At the extreme eastern end of the bridge, where the end span bears on the basalt tip, the design of the foundation was necessarily uncertain. The boulders of basalt made it impracticable to bore or drive piles, and there was no easy means of obtaining samples to determine the strength and degree of consolidation of the clay. Accordingly, excavation for a spread foundation was commenced, and the size and level of the base were determined from observations made as the work proceeded. Eventually it was decided to bear on the clay filling at a pressure of $\frac{1}{2}$ ton per square foot. Roller bearings were provided at this support to ensure concentric loading and avoidance of lateral thrust. Before constructing the foundation, the ground was subjected to severe pounding from a 3-ton piling-hammer, and this treatment produced a preliminary consolidation of about 1 ft. In anticipation of further settlement, the formation was constructed 2 in. high. A settlement of $\frac{1}{2}$ in. had taken place by the time the bridge had been in service for two months, but the total settlement after eight months' service was still only $\frac{1}{2}$ in.

In view of the uncertainties as to what foundations could actually be provided at reasonable cost, the design of the superstructure was not finally decided until after the construction of the various foundations was well advanced.

Superstructure.

The design of the superstructure of the bridge is shown in Fig. 2. The anchor of the whole system is the western box-abutment. The three 81-ft. spans, in conjunction with the western abutment, form a rigid unit. This facilitated the constructional work, which proceeded eastwards from the western abutment. The provision of hinges at the tops and bottoms of the intermediate piers was considered, but this was found to be more expensive than providing rigid joints, despite the horizontal thrusts imparted to the piers by such effects as temperature, shrinking, and braking forces. The piers are deliberately thin (18 in.), and are each




Fig. 3.

2. CAST-IN-SITU REINFORCED CONCRETE
(as adopted)

1. PRESTRESSED
PRECAST
CONCRETE

reinforced differently owing to the different lateral displacements to which they are each subjected. At the eastern face of the Pier No. 3, a pin connection is provided for the short span across to the basalt tip, and this allows for settlement of the foundation on the tip itself. However, the 70-ton braking force from the end span has to be transferred in tension to the western abutment, and this is achieved by the detail indicated at Fig. 2. As a secondary precaution, the end span is prevented from riding off its bearings by reinforced concrete claws which grip under the end stiffening diaphragm of the deck.

Constructional Details.

To assist the proper compaction of the concrete in the beam-ribs, they were cast up to a level $7\frac{1}{2}$ in. below the soffit of the deck slab, and there provided with castellated rebates as shown at Fig. 2. The continuity reinforcement in the top of the deck was fixed subsequently and incorporated in the slab when this was concreted as a separate operation. The castellations have to transfer, between the beam-ribs and the slab, the normal horizontal shearing forces which arise from the bending actions of the bridge deck. However, care had to be taken to prevent shrinking being restricted by the castellations with consequent transverse cracking of the slab, or alternatively the breaking off of the castellations. For this reason the slab was cast in lengths of 40 ft. and precautions were taken to minimise the shrinkage.

The provision of a complete bird-cage scaffolding enabled each span to be in full continuity with its neighbours before the soffit shutters were removed. It also facilitated speedy working, and in fact different stages of the construction on each of the spans were being operated simultaneously.

At one stage there was a report that blasting in the quarry "lifted a man inches off the ground", and it was wondered whether this would be detrimental to the concrete in the earlier stages of hardening. Accordingly a careful watch was kept, and as a result it indicated that the effect of blasting was more psychological than physical, and the man who was lifted off the ground must have been either highly nervous or very agile. However, as a precaution, the

undersides of the parapet copings were recessed $\frac{1}{2}$ in. to provide a key with the insitu walling.

The new approach road on the basalt tip is of flexible construction formed as follows. The tip had to be built up, and advantage was taken of this operation by first laying a basalt sub-base 2 ft. thick, on which was deposited a rolled dry-lean concrete base 12 in. thick, which in turn was covered by an asphalt surfacing 2 $\frac{1}{2}$ in. thick. The sub-base was laid in 9-in. layers and consolidated by an 8-ton roller. The dry-lean concrete base was laid in three 4-in. layers, each of which was consolidated by a vibrating roller weighing 30 cwt. The mixture for the dry-lean concrete is 1 : 22 by weight. The flexible paving has proved entirely satisfactory for carrying the special loading from the very heavy dumpers.

The total cost of the bridge was £65,000. The piling took four months. The pile-caps and the difficult foundations at the western and eastern ends took a further five months. The superstructure, including the western hollow-box abutment, the piers, deck construction, parapets, and the asphalt carriageway, took a further seven months.

The consulting engineers were Messrs. Oscar Faber & Partners. The main contractors were Messrs. McLaughlin & Harvey Ltd. The piles were constructed by The Cementation Co., Ltd.

Reinforced Concrete Association.

THE subject of the meeting of the Reinforced Concrete Association to be held at the Institution of Structural Engineers in London on December 6 is "Watertight Concrete Basements", by L. R. Creasy, B.Sc., M.I.C.E., M.I.Struct.E. The following is a synopsis.

The principles of successful design and construction of basements are reviewed and advice on sealing defects is given. A concrete structure can be made watertight and damp-proof without the assistance of a membrane. Generally the head of water is difficult to predict. The permissible stresses may be increased if the full head to ground level is allowed for in the design.



Aqueduct, Alloz.



Tempul Aqueduct.



Market Hall, Algeciras.

Professor Eduardo Torroja and some of his Works.

(See facing page.)

The Works of the late Professor Eduardo Torroja.

Dr. P. W. ABELES writes:

PROFESSOR EDUARDO TORROJA, whose death occurred in June last, at the age of 61, was one of the few engineers who combined a profound knowledge of the theory and behaviour of structures with architectural imagination. He was one of the first to introduce practical tests of three-dimensional models of structures. He has left, in addition to many structural creations of his design, a valuable book entitled "Philosophy of Structures" in which are described in general terms the basic purposes of structures apart from the technical and computational aspects. He can claim to have introduced prestressed concrete into his works as early as 1925 and he was one of the pioneers of concrete shell construction; his hyperbolic-paraboloidal roofs built in 1935 are famous for their daring appearance due to the extensive cantilevers. The two relative organisations of which Prof. Torroja was president, that is the *Fédération Internationale de la Précontrainte* and the *Association of Shell Structures*, have lost their leader, a loss which was particularly untimely in view of the work in hand in connection with the symposia on model testing and simplified methods of designing shells which were held in Delft and Brussels respectively in August and September of this year. Prof. Torroja was Director of the Technical Institute of Construction and Cement at Madrid, which Institute was founded by him in 1934 and in which he introduced and developed model testing to such an extent that his laboratory has become world famous in this respect.

The few examples of Prof. Torroja's work described in the following are sufficient to show his creative activity and are taken from his autobiography, "The Structures of Eduardo Torroja". Some

of his early works, which are now mainly of historical interest, have been illustrated in past numbers of this journal, and show how soon he became a master in his line. Illustrations of some of these works are given on page 384.

In his first prestressed concrete work, Prof. Torroja used high-strength steel ropes (strand) of 2½ in. diameter. Since this was over thirty-five years ago, this may be considered to be the very first concrete structure in which much of the initial prestress must have remained.

Fig. 1 shows his pioneer prestressed concrete structure, the Tempul Aqueduct, the initial design of which consisted of five equal spans of 66 ft. each, with two river piers supported on piles. Since the authorities did not approve this design, Prof. Torroja changed it by omitting the river piers and including two tie-members each of which is 135 ft. long and extends over a support and is anchored close to an outer pier. The strands, the ends of which were anchored in the concrete, were stressed by jacking them up 10 in. above the supports, thereby lifting the overhanging spans slightly, and at the same time lifting the concrete structure off the centering. Another early example of Prof. Torroja's creative constructions is a prestressed concrete aqueduct built in 1939 at Allox (see page 384 and this journal for October 1948), a structure which is noteworthy not only because of its U-shape but also because of details of the system of forcing apart end-anchored steel members; the system was re-created in Germany under the name "Spreizen" some ten years later. In addition to the strands extending the entire length of the structure, there were pairs of short tensioned strands over the supports and, in addition to the longitudinal prestress,




Fig. 1.—Design of Tempul Aqueduct (1925).

(See also page 384.)




Fig. 2.—Fronton Recoletos (1935).

transverse prestress was also applied by means of turnbuckles. It has been stated that there are no signs of cracking in this aqueduct which is 1340 ft. long.

Cylindrical barrel shells had been introduced in Germany about 1924 by the Zeiss-Dywidag system, but Prof. Torroja was probably the first to develop this idea by the combination of two cylindrical shells with skylights in the roof, as at the Fronton Recoletos in 1935 (Fig. 2); this structure is illustrated in this journal for January 1936. For the skylights a triangulated reinforced concrete structure was provided in which the glass panels were placed. In Fig. 2 it is seen that there is a main girder, which is 11 ft. 6 in. deep and 72 ft. long, provided to support transverse beams from which the lower

balcony is suspended. The roof, which was hit several times during the Spanish civil war, exhibited great resistance, in spite of great deformations, but it eventually collapsed due to buckling caused by progressive creep since it was impossible to shore up the structure in time and to strengthen it. Another construction of the same year is the roof of the Villaverde church (Fig. 3), where a central semi-elliptical shell is connected to two quarter ellipses at each side. The dome of the market at Algeciras (see page 384 and this journal for January 1956) has a diameter of 156 ft. and the shell is only 3½ in. thick. In this structure, Prof. Torroja introduced intentionally, as early as 1933, a stressed ring-beam.

The hyperbolic-paraboloidal cantilevered




Fig. 3.—Villaverde Church (1935).




Fig. 4.—A Preliminary Scheme for the Grandstand, Madrid (1935).

roof (Figs. 4 and 7) of the grandstand, Madrid, built in 1935, is one of the first, if not the first, of this type of currently popular form of construction.

In ordinary reinforced concrete, the Esla bridge of 690 ft. span, built in 1939, was the largest concrete arch at the time and is still the largest railway arch bridge; the crown is 330 ft. above the ground. The arrangement of the centering, which later formed part of the reinforcement of the arch, and jacking apart at the crown are two among a number of novel features.

A further example of how he solved problems with some elegance is seen in Fig. 5, which shows the operating-theatre of the University City Hospital, Madrid, which was built in 1934. The roof covers a circular area of 70 ft. diameter without intermediate columns and a circular skylight of 32 ft. diameter is provided at the centre. In this design, the obvious

solution was discarded and a sound and better alternative, in which ring forces are developed to counteract the cantilever action, was adopted.

Fig. 6 shows an example of Prof. Torroja's recent work, a shell roof for the Tachira Club in Caracas, Venezuela, built in 1957. This double-curved shell has a thickness of 4 in. and is supported on one side by a continuous foundation on roller bearings and by three separate supports. The arches cutting the shell are made rigid by thin ties which allow an open view. Glass panelled façades are provided to act as boundary stiffeners. Rods are provided to resist the horizontal thrust at floor level and longitudinal prestressing above the roller bearings was applied to prevent cracking. By means of the ties all horizontal forces are counter-balanced and vertical forces only are transmitted to the ground.

Since the combination of wisdom and




Fig. 5.—Hospital, Madrid (1934).



Fig. 6.—Tachira Club (1957).



Fig. 7.—Grandstand, Madrid (1935).

modesty had made him a most likable personality, Professor Torroja will be greatly missed not only by his friends but by all those who are interested in the development of new ideas and the co-ordination of theory and practice. The

writer of these notes had the good fortune to be well acquainted with Prof. Torroja.

[NOTE.—Figs. 2 to 6 are reproduced from "The Structures of Eduardo Torroja" by permission of F. W. Dodge Corporation.]

FIFTY YEARS AGO.

From "CONCRETE AND CONSTRUCTIONAL ENGINEERING", November, 1911.

The Destruction of the Austin Dam.

"THE destruction of the Austin Dam on September 30th last has been the subject of a considerable amount of erroneous information in the popular and technical press at home. The dam has been in many cases described as of reinforced concrete. It was nothing of the sort. It was a concrete structure which had at certain points been slightly reinforced with metal. Secondly, certain other papers commented upon the accident as being due to the fact that it was of concrete. This, again, is erroneous, for the failure was not due to the body of the dam at all, but to unsatisfactory foundations. Besides, the dam had already failed to a certain extent long before the disaster of September 30th, and, owing to delay for some inexplicable reasons, the damage had not been made good.

American technical papers reiterate the fact that it was due to faulty foundations, the dam having slid forward on its base until it toppled over."

The New Grandstand at Ascot.




FIG. 1.

CONCRETE has been used in many ways and for varying purposes in the new Queen Elizabeth II stand (Fig. 1) at Ascot racecourse which was opened in June last. The constructional period was only ten months and the tight programme required that as many as possible of the structural components should be prepared before work commenced on the site. Consequently the floors, terraces, stairs to the boxes, balcony balustrades and some flights of main stairs are of precast concrete. The main structure and roof

are of structural steelwork, the main frame being encased in concrete for fire protection and in order to reduce maintenance. The grandstand comprises two main parts. The principal section, which faces the racecourse, is 560 ft. long and 80 ft. wide, and has an average height of 74 ft. Centrally at the rear of this section there is a circulation area one third as long. At the front of the main section, the terrace (Figs. 2 and 3), which accommodates 8000 persons standing, rises in steps at a slope of 1 in 2.



Fig. 2.




Fig. 3.

Precast Construction.

The steps of the terrace are constructed of hollow precast reinforced concrete units (Fig. 4) and, because of the pedestrian traffic to which they are subjected, the slab over the cavity is $1\frac{1}{2}$ in. thick. For rigidity, a span of 10 ft. has been adopted for this section, which is half the basic span elsewhere throughout the structure. The steps overlap one another, with the overlap bedded and pointed in mortar, and are coated with asphalt. Behind the terraces is an area occupied by stall seats supported on a continuation of the raking beams of the terrace. The seats are bolted to ell-shaped precast reinforced concrete units each forming the going and the riser of a step (Fig. 5). These units are of concrete having a strength of 4000 lb. per square inch at twenty-eight days. The balustrade in front of the stalls is of concrete precast in panels and ribbed vertically on the outer face (Fig. 6), which pattern is repeated for most of the vertical panels throughout the grandstand.

The main structure behind the terraces comprises seven main floors which are of suspended construction and include

ground and mezzanine floors, and five private dining-room floors, which serve the boxes on three balconies. The middle dining-room floor is at the same level as the adjacent balcony, but access from the remaining upper and lower dining-room floors to the boxes is by means of




Fig. 4.

November, 1961.



Fig. 5.—Precast Seating.

short flights of steps. The main floor slabs spanning between the steel beams are prestressed hollow precast units (Fig. 4), 3 ft. 2 in. wide and 7½ in. deep; they contain cables of pretensioned 0.2-in. crimped wires and span 20 ft. The slabs, in each of which are three cavities, were made by the long-line method. Since the soffits were painted after erection, the units were cast in special steel moulds with bold arrises. The crushing strength of cubes of the concrete for these slabs was 6000 lb. per square inch at twenty-eight days, the strength at transfer being 4000 lb. per square inch. The imposed design load is 100 lb. per square foot throughout the floors except in the private dining rooms and boxes where it is 80 lb. per square foot. Load tests and handling tests were carried out on prototypes of the units. To reduce the storey heights, the floor beams are laid with their tops 1 in. above the top of the supporting steel beams and are seated on rebates in the concrete encasing the beams. The width of the seating of the slabs is 2½ in. since

it was necessary to insert the slabs under the top flanges of the beams and, because of this, to allow for a tolerance in positioning the slabs. The total area of precast flooring and terraces is 17,000 sq. yd. which requires 4600 units. The units were cast to very close dimensional tolerances.

The balcony balustrade (Fig. 6) extends the full length of the grandstand and comprises 168 precast ribbed panels each 10 ft. long. The panels were lifted into place by being slung from gear engaging with bolts in the top edge (Fig. 7); the bolts were afterwards used to attach a hardwood cap-rail. The panels were temporarily maintained in a vertical position by two tapped studs welded to the top flange of the steel channel which supported them. The permanent fixing of the panels to resist bending was effected by reinforcing bars protruding horizontally from the panels and embedded in the 2-in. structural topping on the first two precast slabs of the balcony floor; these two slabs differed from the ordinary slabs for the balcony, in so far that they are



Fig. 6.—Precast Balustrade.



Fig. 7.—Lower Box-balcony.

prestressed hollow beams 1 ft. 9 in. wide with a key formed between them to provide a mechanical bond with the topping. The rear balconies giving access to the dining-room floors have balustrade panels similar to those of the box balconies, but greater in height, and are fixed in a similar manner.

Included in the precast construction are the five different types of units forming parts of the access from the dining rooms to the boxes at the split-levels (Fig. 8). In each 20-ft. bay these units comprise four stairs (two up and two down), solid panels alongside the downward flights, and panels filling the triangular space between the flights; the latter panels are in two pieces for ease of handling. The concrete of the stairs contains granite aggregate and has a finish of carborundum trowelled into the treads.

It was necessary to stockpile all precast units before work commenced on the site in order to avoid delays.

Encased Steelwork.

The concrete encasing the steelwork provides a minimum cover of 2 in. over the steel. The casing of the stanchions (Fig. 9) is generally reinforced with high-tensile welded fabric weighing 1 lb. per square yard, but is increased to comply with the requirements of B.S. No. 449 where the concrete casing is taken into account in assisting the load-bearing capacity of the encased stanchions, as is necessary in a few cases where it is desirable to have the stanchions all of the same section. The concrete for the casings is a nominal 1 : 2 : 4 mixture with a $\frac{3}{4}$ -in.

aggregate, and has a strength of 3000 lb. per square inch at twenty-eight days; the proportions were selected after tests of workability and strength. The concrete encasing the steel beams is reinforced and secured by fabric similar to that used for the stanchions. Where the casing envelopes only the lower part of a beam, $\frac{1}{2}$ -in. diameter mild steel bars pass through holes drilled in the web of the beam to secure the reinforcement and the casing.

Cast-insitu Construction.

In addition to the large extent of precast work there are some parts, mainly stairs and landings, which are of ordinary cast-insitu construction generally of 1 : 1½ : 3 reinforced concrete.

One of the two pairs of escalators is external and is contained in a reinforced



Fig. 8.—Stairways of Precast Units.




Fig. 9.—Encased Steelwork supporting Prestressed Concrete Floors.

concrete trough (Fig. 11) which also acts as the beam to support the stair and spans between the levels of the ground and mezzanine floors. This construction also carries parallel stairs which cantilever from it on either side. The concrete for this work is 1 : 1½ : 3 with ¾-in. aggregate.

Foundations.

The foundations are in the sand and sandy gravel of the Bagshot series and are at a relatively shallow depth. The net bearing pressure is 1½ tons per square foot. The main foundations, where separate from those of the walls, are in the form of independent pads and continuous strips. The independent pads are of ordinary reinforced concrete design and comprise 1 : 2 : 4 concrete with 1½-in. aggregate and are laid on a 1 : 12 blinding

concrete. The largest pads are 13 ft. 6 in. square. The continuous strip foundations are 8 ft. wide by 6 ft. deep and are of 1 : 10 concrete with 1½-in. aggregate. Construction joints were formed at the third-points between the stanchions to suit the amount of concrete placed in one operation. High-tensile fabric weighing 10·76 lb. per square yard is provided in the bottom. At the position of each stanchion, a pocket was formed to receive a pad of 1 : 2 : 4 concrete which acts as a seating for the steelwork and contains the holding-down bolts; to distribute the loading from these pads, 1-in. diameter mild steel bars are provided in the concrete strip footing below the pockets.

Other foundations in the circulation area are combined one with another and with the lift pits and the retaining walls



Fig. 10.—Construction of Basement Floors.




Fig. 11.—Cast-insitu Construction of Escalator Supports and Stairs.

in this area, where a basement is provided. The stanchions form piers for the walls which span between them. Because of the low water-table, no tanking was applied to the basement walls which are reinforced with high-tensile fabric and constructed in 1 : 1½ : 3 concrete. P.V.C. water-bars are provided in all construction joints.

Work in progress on the construction of the basement slabs, which are laid on sheets of polythene on the ground, is shown in Fig. 10.

The main contractors were Messrs. George Wimpey & Co., Ltd., who were also responsible for the structural design. Sub-contractors for the precast concrete work were Concrete (Southern) Ltd., for the units for the floors and terraces, and Messrs. Cawood Wharton & Co., Ltd., and Messrs. John Ellis & Sons, Ltd., for stalls, stairs and panels. The two tower-crane were Pingo cranes.

The information in the foregoing is contributed by Mr. D. DENNINGTON, B.Sc., A.M.I.C.E.

Bulletins Received.

- "Country Roads Board.—Forty-Seventh Annual Report." (Melbourne, Australia: 1961. No price stated.)
- "Co-operation Between Main Contractors and Sub-Contractors in the Building Industry." (London: National Federation of Building Trades Employers. 1961. Price 2s. 6d.)
- "The Professional Engineer—His Employment and Development." (London: The Engineers' Guild Ltd. 1961. Price 7s. 6d.)

The following documents are published by H.M.S.O. (London, 1961) for the Ministry of Labour.

- "Factories Acts, 1937-1959 Report—Lifting and Construction Regulations." (Price 3s.)
- "Factories.—The Construction (General Provisions) Regulations No. 1580, 1961." (Price 9d.)
- "Factories.—The Construction (Lifting Operations) Regulations No. 1581, 1961." (Price 1s.)

Permissible Stresses in Road Bridges.

THE Ministry of Transport have announced that the permissible working stresses in concrete and reinforcing bars in road bridges and structures have been revised by the Bridges Committee of the Road Research Board and are accepted by the Ministry as being applicable to designs which require the Ministry's approval. The revised stresses, which are to be used in conjunction with the loads described in Memorandum No. 771,* are given in a new Memorandum No. 785, "Permissible Working Stresses in Concrete and Reinforcing Bars for Highway Bridges and Structures". The recommendations are in a form suitable for a code of practice, and their adoption necessitates replacement of certain clauses in the Ministry's Standard Specification. The sections of Memorandum No. 577, "Bridge Design and Construction", relating to concrete are now superseded.

Permissible Stresses in Reinforcement.

LOADING TYPE HA. (B.S. No. 153, Part 3, Section A—1954).—In mild steel bars complying with B.S. No. 785, the stresses in tension and compression should not exceed 18,000 lb. per square inch for bars of all sizes. In cold-twisted steel bars complying with B.S. No. 1144 and for deformed bars of high-tensile steel with a guaranteed yield-stress, the stress in tension should not exceed half the guaranteed yield-stress or 30,000 lb. per square inch, whichever is less. The stress in compression should not exceed half the guaranteed yield-stress nor be more than 23,000 lb. per square inch.

CRACK CONTROL.—When the reinforcement is of steel other than mild steel and when the stress exceeds 18,000 lb. per square inch in tension, the arrangement of bars determined from the stress calculations should be checked for crack control by applying the formula

$$T = \frac{n l_a E_s \sqrt{D}}{Z f_s}$$

where

n = number of bars in tension in the section; where bars in slabs are

* Memorandum No. 771, "Standard Highway Loads".

spaced uniformly, n is equal to 12 in. divided by the distance (inch) between centres of adjacent bars,

l_a = lever arm (inch) measured to the centroid of the reinforcement,

E_s = modulus of elasticity of the steel (lb. per square inch),

Z = section modulus (in.³) of the whole section with regard to the edge which is in tension, as if it were plain concrete; for slabs, a width of 12 in. is taken,

f_s = stress (lb. per square inch) in reinforcement at cracked section, at the centroid of the reinforcement,

D = diameter of the reinforcing bar (inch).

Minimum acceptable values of T (in inch units) are as follows.

	Deformed Bars	Cold-twisted Bars
Dead load . . .	105	140
Dead load + live load . . .	70	90

If bars in beams are of different sizes, the calculations should be carried out for each group of bars of the same size and the values of T added together.

LOADING TYPE HB. (B.S. No. 153, Part 3, Section A—1954).—The maximum stresses permitted for loading type HA may be increased by 25 per cent., but should not exceed 30,000 lb. per square inch in tension or 23,000 lb. per square inch in compression.

Permissible Stresses in Concrete.

The compressive, shearing and bond stresses in reinforced concrete should not exceed those given in Table I. The permissible bond stresses may be increased by 25 per cent. when cold-twisted bars and deformed bars are used. When the proportions of total aggregate to cement are between those given in Table I, the permissible concrete stresses should be based on the ratio of the sum of the volumes of the fine and coarse aggregate, measured separately, to the quantity of cement and should be obtained by proportion from the two nearest nominal proportions.

TABLE I

Nominal proportions			Aggregate per 112 lb. of cement (cu. ft.)		Cube strength within 28 days after mixing (lb. per sq. in.)		Cube strength within 7 days after mixing (lb. per sq. in.)		Permissible concrete stresses (lb. per sq. in.)				
Cement (lb.)	Fine Aggregate (cu. ft.)	Coarse Aggregate (cu. ft.)	Fine	Coarse	Preliminary test	Works test	Preliminary test	Works test	Compression		Shearing	Bond	
									Direct	Due to bending		Average	Local
150	2	4	1½	3	5600	4300	3750	2800	1060	1400	125	145	210
120	2	4	1½	3½	5000	3750	3350	2500	950	1250	115	135	200
90	2	4	2½	5	4000	3000	2700	2000	760	1000	100	120	180

When considering the effect of loading type HB, it is permissible to allow an overstress of 25 per cent.

Consideration will be given to the use of higher working stresses in special cases provided there are adequate safeguards

to ensure sufficiently close control of the quality and workmanship of the concrete.

References to B.S. No. 153, Part 3, Section A (1954), should be read in conjunction with Ministry of Transport Memorandum No. 771.

International Association for Bridge and Structural Engineering.

PAPERS of interest to reinforced concrete engineers published in the twentieth volume (1960) of the "Publications" of the International Association for Bridge and Structural Engineering, include the following.

"A General Analysis of Elasto-Plastic Three-Dimensional Frames." By A. L. L. Baker (Great Britain; in English).

"Theory of Shells of any Shape." By E. Bolcskei (Hungary; in German).

"Calculation of Groups of Piles with a Non-Linear Relationship Between Force and Penetration." By E. Gruber (Germany; in German).

"Curved Edge Disturbances in Circular Cylindrical Shells." By I. Holand (Norway; in English).

"Spherical Domes Under Unsymmetrical Loading." By T. van Langendonck (Brazil; in English).

"The Vibrations of Massive Foundations on Soil." By M. Novak (Czechoslovakia; in English).

"Membrane Stresses in Hyperbolic Paraboloid Shells Circular in Plan." By

E. P. Popov and S. J. Medwadowski (U.S.A.; in English).

"Elasto-Plastic Analysis of an Inter-connected Beam System." By D. V. Reddy and A. W. Hendry (Great Britain; in English).

"Abnormal Loading on Two Types of Short Span Bridge." By R. E. Rowe (Great Britain; in English).

"Strength Calculation of Reinforced Concrete Structures." By Y. Saillard (France; in French). Preparation of standards; Report on the work of the 5th Meeting of European Committee on Concrete.

"On the Relaxation of Steel Wires." By F. Speck (Switzerland; in German).

Copies of "Publications of the International Association for Bridge and Structural Engineering," Volume 20, 1960 (price 45 Swiss francs), are obtainable from Verlag Leemann, Zürich. "Publications" contains eighteen papers of which twelve are in English, two in French and four in German. Each paper is followed by a summary in each of these languages.

The Design of Doubly-reinforced Flanged Beams by the Load-factor Method.

By YÜKSEL SEZGINER, Dipl. Ing. (Turkey).

THE nomogram on pages 398 and 399 applies to the design of doubly-reinforced beams of tee, ell or I section by the load-factor method, and is based on the following equations.

$$\frac{M_r}{p_{cb} b d_1^2} = \frac{b_r}{4b} + \frac{1}{3} \left(1 - \frac{b_r}{b} \right) \left[2 \frac{d_2}{d_1} - \left(\frac{d_2}{d_1} \right)^2 \right] + R_{sc} r_{sc} \left(1 - \frac{d_2}{d_1} \right) \quad (1)$$

$$r_{st} R_{st} = \frac{2 \left[\frac{d_2}{d_1} + \frac{b_r}{b} \left(1 - \frac{d_2}{d_1} \right) \right]}{3 \left[\frac{d_2}{d_1} + \frac{b_r}{b} \left(1 - \frac{d_2}{d_1} \right) \right]} + r_{sc} R_{sc} \quad (2)$$

in which $r_{sc} = \frac{A_{sc}}{b d_1}$, $R_{sc} = \frac{p_{sc}}{p_{cb}}$, $r_{st} = \frac{A_{st}}{b d_1}$, and $R_{st} = \frac{p_{st}}{p_{cb}}$. The use of the nomogram is explained by the examples which follow.




Fig. 1.




Fig. 2.

EXAMPLE I.—Determine the amount of reinforcement required in the I-beam in Fig. 1 if it is subjected to a bending moment of 4,725,000 in.-lb. The permissible stresses are $p_{cb} = 1000$ lb., $p_{st} = 20,000$ lb., and $p_{sc} = 18,000$ lb. per square inch.


First step.—Calculate the ratios for use with the nomogram, namely,


$$\frac{b}{b_r} = \frac{21}{7} = 3; \frac{d_2}{d_1} = \frac{26}{30} = 0.87; \frac{d_2}{d_1} = \frac{1.5}{30} = 0.05; R_{sc} = 18;$$

$$\frac{M_r}{p_{cb} b d_1^2} = \frac{4,725,000}{1000 \times 21 \times 900} = 0.250; \text{ and } R_{st} = 20.$$

Second step.—Intersect the vertical line for $\frac{b}{b_r} = 2.0$ at 0.163 by a horizontal line drawn from the intersection of the lines for $\frac{b}{b_r} = 3$ and $\frac{d_2}{d_1} = 0.20$.

Connect the point for 0.163 with $\frac{M_r}{p_{cb} b d_1^2} = 0.250$ and produce the line until it cuts the vertical line for $\frac{d_2}{d_1} = 0$ at 0.087. A horizontal line drawn from this point to intersect the line for $\frac{d_2}{d_1} = 0.05$ at $R_{sc} r_{sc} = 0.092$. Produce it on to the





vertical line for $\frac{d_2}{d_1} = 0$ by a parallel line. A_{sc} can be calculated from

$$A_{sc} = \frac{0.092 \times 21 \times 30}{18} = 3.22 \text{ sq. in.}; \text{ provide five 1-in. bars.}$$

Third step.—Connect 0.092 with the point for $\frac{d_2}{d_1} = 0.20$. The line intersects the vertical for $\frac{b}{b_r} = 3$ at $r_{st}R_{st} = 0.292$. Then $A_{st} = \frac{0.292 \times 21 \times 30}{20} = 9.20$ sq. in.; provide six 1½-in. bars.

EXAMPLE II.—The tee-beam in Fig. 2 is subjected to a bending moment of 1,375,000 in.-lb. Assuming $p_{cb} = 1000$ lb. per square inch, check that the stresses in the tension and compression reinforcement do not exceed 30,000 lb. and 23,000 lb. per square inch respectively.

First step.—Calculate the necessary ratios for use with the nomogram, namely,

$$\frac{b}{b_r} = 4, \frac{d_2}{d_1} = \frac{3}{12} = 0.25; \frac{M_r}{p_{cb}bd_1^2} = \frac{1,375,000}{1000 \times 36 \times 144} = 0.265; \frac{d_2}{d_1} = \frac{1.5}{12} = 0.125;$$

$$r_{st} = \frac{4.91}{36 \times 12} = \frac{1.137}{100}; \text{ and } r_{sc} = \frac{2.36}{36 \times 12} = \frac{0.546}{100}.$$




Fig. 3.

Second step.—By the same procedure as in Example I, obtain $r_{sc}R_{sc} = 0.106$. Therefore the amount of compression reinforcement required, with

$$R_{sc} = \frac{23,000}{1000} = 23,$$

is given by $A_{sc} = \frac{0.106 \times 36 \times 12}{23} = 1.99$ sq. in.;

since the area provided is 2.36 sq. in., the stress is less than 23,000 lb. per square inch.

Third step.—By the same procedure as in Example I obtain $r_{st}R_{st} = 0.315$, $R_{st} = \frac{31.5}{1.137} = 27.70$, and $p_{st} = 27,700$ lb. per square inch.

Basis of Equations.

Equation (1) differs in form from equation (6) in the B.S. Code No. 114 which is

$$M_r = \gamma p_{cb}bd_1^2 + A_{sc}p_{sc}(d_1 - d_2).$$

The first part of this equation is the moment of resistance of a flanged beam,

The £.s.d of OSAL*

—Hardening New Floor Toppings.

**It's not the cost
per gallon
but
the cost per yard
that counts**

On this basis Tricosal, which hardens a square yard of 3/1 sand and cement screed or granolithic paving 1" thick for only 7½d., is the most economical as well as the most efficient additive. It hardens integrally and, being a liquid, mixes with the gauging fluid and is evenly distributed throughout the mix.



For 30 years or more Tricosal has been specified by leading Architects not only for hardening but for water-proofing cement and concrete and increasing their resistance to oils and acids. Send for Information Leaflet No. 1.

** Osal is the generic name for the products of A. A. BYRD & CO. LTD.—Florosol, Neocosol, Tricosal and Lubrosal. Literature about each individual product is available on request.*

A. A. BYRD & CO. LTD. (Dept C11) 210 TERMINAL HOUSE, GROSVENOR GARDENS, LONDON, S.W.1

Phone: SLOane 5236

Grams: Byrdloom, Wesphone, London • Works: Basingstoke, Hants



FOR SEWERAGE WORK

USE
HIGH
QUALITY
CONCRETE
AND
MORTARS
MADE
WITH

*Highly resistant to acidic effluents

*Need no waterproofing compounds—they should not be used

*Completely immune to any concentration of sulphates
and most acidic ground conditions

NOTE: All concrete required to resist chemical attack
should be dense and satisfactorily cured



HIGH ALUMINA CEMENT TO BSS 915

LAFARGE ALUMINOUS CEMENT COMPANY LIMITED • 73 Brook Street • London W1 • Tel: MAYfair 9548
API52

with tension reinforcement only, based on the compressive resistance of the concrete. The force in the reinforcement in this case has to be balanced by the resistance of the concrete (Fig. 3). If the cross-sectional area of this reinforcement is A_{st1} the following formula can be derived.

$$A_{st1} p_{st} = \frac{2}{3} p_{cb} \left[(b - b_r) d_s + b_r \frac{d_1}{2} \right]$$

from which
$$\frac{A_{st1} p_{st}}{p_{cb} b d_1} = r_{st1} R_{st} = \frac{2}{3} \left[\frac{d_s}{d_1} + \frac{b_r}{b} \left(\frac{1}{2} - \frac{d_s}{d_1} \right) \right].$$

In the case of a beam with compression reinforcement, the total amount of tension reinforcement is $A_{st} = A_{st1} + A_{sc} \frac{p_{sc}}{p_{st}}$. Also $r_{st} R_{st} = r_{st1} R_{st} + r_{sc} R_{sc}$.

From the preceding equation, $r_{st} R_{st} = \frac{2}{3} \left[\frac{d_s}{d_1} + \frac{b_r}{b} \left(\frac{1}{2} - \frac{d_s}{d_1} \right) \right] + r_{sc} R_{sc}$, which is equation (2).

"Effects of Differential Temperature on Tall Slender Columns."

MR. A. J. ASHDOWN writes as follows.

Since I contributed an article on thermal stresses in this journal for August 1933, the article by Mr. D. A. Stephenson in the number for May 1961 is of particular interest to me. The suggestion that the temperature through the concrete varies exponentially is new to me and it would be interesting to know how the factor $a = \sqrt{\frac{1}{2} \omega C R}$ is derived; the effect of dispersion of heat through the ends is not included. There seems to be a great difference between a linear variation and an exponential variation of thermal strain, especially so for thick concrete members. Experimental and analytical evidence for assuming an exponential variation would be of great interest, as recent experiments carried out at the Imperial College, London, indicate a perfectly linear variation of temperature through concrete 13 in. thick, with the sides of the specimen insulated against heat loss. If the assumption of an exponential variation is valid, the assumption that the moments due to heat-strain and linear strain about the cool face are equal is convenient but is difficult to justify.

If plane sections remain plane after the imposition of an exponential distribution of heat-strain, internal stresses will be set up. In order to determine these stresses, two conditions must be satisfied, namely, that there is no difference of strain between the exponential heat-strain and a linear strain, and that the moments caused by these strains and acting about the centroid of the section should balance. The second condition will cause a strain αT_n to act at the cool face. The heat-strain at any point at a distance x from the hot face is $\alpha T_0 e^{-ax}$. The equivalent linear strain is

$$\alpha T_n + \alpha (T_1 - T_n) \left(1 - \frac{x}{d} \right).$$

The difference of strain is


$$\alpha T_0 e^{-ax} - \alpha T_n - \alpha (T_1 - T_n) \left(1 - \frac{x}{d} \right). \quad (a)$$

Then from the first condition, the integral of expression (a) gives the total difference of strain which is

$$\alpha T_0 \left(\frac{1}{a} - \frac{e^{-ad}}{a} \right) - \alpha T_n d - \alpha (T_1 - T_n) \frac{d}{2} = 0, \quad (b)$$

whence

$$T_1 - T_n = \frac{2 T_0}{d} \left(\frac{1}{a} - \frac{e^{-ad}}{a} \right) - 2 T_n. \quad (c)$$



Also from the second condition

$$\int_0^d \alpha T e^{-ax} \left(\frac{d}{2} - x \right) - \alpha T_n \left(\frac{d}{2} - x \right) - \alpha (T_1 - T_n) \left(\frac{d}{2} - \frac{3}{2}x + \frac{x^2}{d} \right) dx = 0,$$

from which $\alpha T_0 \left(\frac{e^{-ad}}{a^2} + \frac{de^{-ad}}{2a} + \frac{d}{2a} - \frac{1}{a^2} \right) - \alpha (T_1 - T_n) \frac{d^2}{12} = 0.$

Substituting the value of $T_1 - T_n$ from equation (c) and reducing,

$$\alpha T_0 \left(\frac{e^{-ad}}{a^2} + \frac{2de^{-ad}}{3a} + \frac{d}{3a} - \frac{1}{a^2} \right) + \frac{\alpha d^2 T_n}{6} = 0 \quad (d)$$

In the example given in the article, this expression reduces to $\frac{T_0}{6} + \frac{6.25T_n}{6} = 0$, hence $T_n = -0.16T_0$, and from equation (c),

$$T_1 + 0.16T_0 = \frac{2}{ad}T_0 + 0.32T_0.$$

Thus

$$T_1 = (0.267 + 0.16)T_0 = 0.427T_0.$$

The stress at any point is

$$E\alpha T_0 \left[e^{-ax} + 0.16 - 0.587 \left(1 - \frac{x}{2.5} \right) \right] \quad (e)$$

Positive results indicate compressive stresses and the distribution is shown in the accompanying diagram.

The radius of curvature is

$$\frac{d}{\alpha(T_1 - T_n)} = \frac{2.5}{(0.427 + 0.16)12 \times 5.5 \times 10^{-6}} = 64,500 \text{ ft.}$$

The deflection at the column-head due to free curvature is

$$\frac{120^2}{2 \times 64,500} = 0.114 \text{ ft.} = 1.34 \text{ in.}$$

The maximum restraint stresses, adopting the value for E given in the article, are ± 160 lb. per square inch, to which must be added the stresses found from expression (e). The stress at the hot face is $(0.573 \times 12 \times \alpha E) + 160 = 208 + 160 = 368$ lb. per square inch, and at the cool face is $(0.160 \times 12 \times \alpha E) - 160 = 58 - 160 = -102$ lb. per square inch. Since the column is in direct compression, probably no tensile stresses occur.

There is an error in the integration of formula (1) which should be

$$T_0 \alpha \left[\frac{e^{-ad}}{a^2} + \frac{d}{a} - \frac{1}{a^2} \right]$$

When the Designer consults the Mould Maker

Before the Engineer completes a design incorporating precast structural members he can be certain that his intentions will be executed by the soundest and most economical methods if he has the advice of an experienced mould maker. Ease of stripping; accuracy; regularity of quality of concrete unit; constant use of moulds; maximum interchangeability of moulds; minimum expenditure of labour: these factors vitally affect final cost. We specialise in the design of moulds for all types of precast structural members, and are always at the service of Designers who wish to ensure that their designs can be properly and economically carried out.

**STELMO**

*the most comprehensive
mould service in the world*

STELMO LTD • WESTWELL LEACON • CHARING • ASHFORD • KENT. Tel: Charing 395-7



Compare
this penetrating
ability * with anything you have ever used before

* ROTOPUNCH PENETRATION

Material	depth	time
Granite	2"	3 mins.
Concrete	1½"	30 secs.
Hard Brick	2½"	30 secs.
Stone (Portland)	2½"	30 secs.
Soft Brick	1½"	15 secs.
Breeze-block	2½"	15 secs.

Using a 1" drill

- Produces quick, clean holes in all types of constructional materials.
- Ideal for fixing wall attachments, making entrances for pipes and fittings, grouting down machinery.
- Two tools in one—easy, fast change from percussion to normal drilling.
- Operator comfort is assured by the well balanced design and light weight.
- Low-cost—high productivity.

The unique

Wolf

ROTOPUNCH

ROTARY PERCUSSION DRILL

The Drill with the power to pierce granite



The versatile "Rotopunch" can help you and your business. So fill in the coupon NOW for an illustrated leaflet giving facts and benefits in detail—and POST TODAY.

TO: WOLF ELECTRIC TOOLS LTD., Dept. C.C.E.11,
Pioneer Works, Hanger Lane, London, W.5.
Please send me the illustrated leaflet on the "ROTOPUNCH"

COMPANY _____

ADDRESS _____

MARK FOR THE ATTENTION OF _____

Branches at: BIRMINGHAM • BRISTOL • GLASGOW • LEEDS • MANCHESTER • NEWCASTLE • Agents throughout the World

and should be repeated in formula (2). Although in the example the correct numerical solution is obtained, the expression should read

$$12x \int_0^{2.5} e^{-0.2x}(2.5 - x)dx = 12x \left[\frac{e^{-2.5}}{9} + \frac{2.5}{3} - \frac{1}{9} \right] = 12x \times \frac{11}{18}.$$

The assumption of an initial value of E of 5.5×10^6 seems rather high; a value of 4.2×10^6 for concrete with a cube-strength of 6000 lb. per square inch is more correct. Prestressing concrete may not alter the modulus of elasticity but high prestress may lower its initial value.

Mr. D. A. STEPHENSON replies as follows.

The basic theory of heat flow does, of course, assume a linear variation of temperature through a conductor, since the rate of heat transmission, which must be constant along its path, is proportional to the temperature gradient. The point that Mr. Ashdown appears to have missed is that in practice all conductors have thermal capacity and, because of this, the temperature gradient does not become uniform until conditions of equilibrium have been achieved, which is after an appreciable lapse of time. If the temperature at the surface fluctuates during this period, the variations of temperature within the conductor, both with time and with distance from the surface, are more complex than in the idealised case upon which the principles of thermal conduction are based. For example, it would be possible to raise the surface temperature of a thick concrete wall to several hundred degrees C. almost instantaneously by allowing numerous blow-lamps to heat it, but it would not be expected that the temperature at the middle of the wall would rise equally quickly to one half of the surface temperature.

For the theoretical justification of the heat-flow formulae, reference should be made to a text-book such as 'Elements of Heat Transfer' by Jacob and Hawkins and the experimental work carried out in Kuwait by the Building Research Station of D.S.I.R.

I agree that my assumption of zero strain at the cool face is inaccurate, and thank Mr. Ashdown for drawing attention to this matter. I also agree that the second term within the square bracket in formulae (1) and (2) should be $+\frac{d}{a}$.

The value of E used in the example is based on that used in the case of the main columns of the viaduct of the Tasman Bridge now being constructed at Hobart, Tasmania. A value of 5.5×10^6 was adopted after careful collation of experimental data and relates to concrete having a specified minimum cube-strength of 6500 lb. per square inch at twenty-eight days. The figure suggested by Mr. Ashdown corresponds to an American formula $E = (1.8 \times 10^6) + 390u$, which is generally recognised as giving low values.

Lectures on Building.

THE following lectures have been arranged by the Ministry of Works. Admission is free. The meetings commence at 7.15 p.m. unless stated otherwise.

Prevention of Accidents in the Building Industry. By J. A. Hayward. Technical College, Bolton. November 16; Technical College, Connahs Quay. November 21, 7 p.m.; Technical College, Wrexham. November 22, 7 p.m.; and the Westminster Hotel, Rhyl. November 23.

New Techniques in Building. By D. Bishop. Highbury Technical College, Anglesea Road, Portsmouth. November 20.

Fire Resistance of Concrete Structures. By N. R. Hollington. Technical College, Southampton. November 21.

Work Study Aids Builders. By B. D. Wakeford. Technical College, Waterdale, Doncaster. November 22; and Technical College, Wakefield. November 23.

Work Study in the Building Industry. By K. C. M. Symons. Technical Institute, Bognor Regis. November 29.

Good Concrete From Local Aggregates. By R. Cameron. Y.M.C.A., Newcastle-upon-Tyne. November 30.

Box-frame Construction in Sweden.

To reduce cost and amount of labour required, a method of construction utilising a concrete box-frame is being used increasingly in Sweden. Although used mainly for residential structures it is said to be adaptable to any structure where repetition occurs. The illustration in Fig. 2 is of a students' hostel at Lund.

Standard shuttering of room-size for casting the floors and internal cross-walls is assembled on the ground and hoisted into position by crane. The shuttering

is faced with plastic-faced plywood and is fitted with the necessary bolts, clamps and jacks; there is also a platform from which the concrete is placed to form a monolithic box-frame structure. The shuttering is easily removed for further use. Heating coils are embedded in the floor slab during construction and other services are incorporated in the floors and walls. Interior fittings are bolted to threaded sleeves embedded in the concrete. Items such as chutes, ducts and



Fig. 1.

FOUR OUT OF FIVE LARGE

Strand

contracts in the U.K. use CCL anchorages





Spiral anchorages

CCL Spiral Anchorages are used extensively, both at home and overseas, due to their advanced design and reliability under site conditions. These all-metal, embedded type anchorages provide additional safety against bad concrete compaction.

For further or helpful advice or technical information write to:

CABLE COVERS LIMITED • St Stephen's House • (Technical Service Dept) • Westminster S.W.1





Pattern of service in the concrete age

*Hand-cut and placed Serpentine marble slips
cast integrally with structural H-frames
for St. Thomas' Hospital redevelopment.*

Consulting Engineers *F. J. Samuely & Partners*
Architect *W. Fowler-Howitt, Dip. Arch. A.R.I.B.A.*
Main Contractor *Gilbert-Ash Limited*

Three Fold Service

Modular offer the combined services of consultation,
design, manufacture and erection

Modular will manufacture and erect to your designs

Modular are specialists in precast structural concrete
combined with integral finishes

Whatever your concrete problem, The Modular Concrete
Company's practical experience and technical
resources are at your service.



Specialist Engineers and Contractors

THE MODULAR CONCRETE CO. LTD.

Precast Division, Staines Road, Bedfont, Middlesex. Telephone: Ashford (AS 9) 5631



Fig. 2.




Fig. 3.

stairs are placed in position by a crane before the shuttering is re-erected for a further storey. *Fig. 1* shows a panel of shuttering being placed in position by means of a crane. Details of the panels and the working platform attached thereto are shown in *Fig. 3*. The structures shown in *Figs. 1* and *3* are at Edsburg.

A feature of the method of construction is that finishing work proceeds simultaneously with construction. Floor slabs are screeded, finished and polished by a machine before the next lift of the walls is cast. The plastic-faced shutters leave a surface which can be painted or wallpapered after a simple polishing operation. Exterior walls are usually of precast concrete panels $3\frac{1}{2}$ in. thick, and sandwiched between this facing and the interior finish of plasterboard backed by aluminium foil is a 4-in. insulating layer of rock-wool. Precast panels of various finishes are used or alternatively brick infilling is used. An




Fig. 4.

example of the latest applications is the construction of residential buildings in Malmö which include five buildings with from five to twenty-five storeys, containing shops, offices, tennis courts and a large garage in addition to upwards of seven hundred flats. The illustration in Fig. 4 is of one of these multiple-storey buildings in the course of construction.

AB Skånska Cementgjuteriet, a firm of Swedish contractors, developed the method, which is known as the "Allbetong" method, in the early 1950's and claim that by its use the number of man-hours required for a given volume of building has been reduced by about half compared with conventional constructional methods.

Ready Reckoners.

REVISED British Standard B.S. 1151 (Part 2—1961), "Guaranteed Minimum Reckoners for the Building and Civil Engineering Contracting Industries", was published recently. The revision is necessitated by the adoption, from October 2, by the building industry of a 42-hour week in place of a 44-hour week. The reckoner facilitates calculation by the formula

$G = \frac{36W}{N}$, where G = the number of hours guaranteed, W = the number of working hours available, and N = the number of normal hours specified in the working-rule agreements.

Copies of the Standard are obtainable from the British Standards Institution, 2 Park Street, London, W.1; price 3s.

What **POZZOLITH** means to you


POZZOLITH has contributed to the building of many magnificent concrete structures. With modern building becoming increasingly adventurous, builders are demanding a more versatile, more pliable concrete. **POZZOLITH** is helping to meet this demand ... enabling users to exercise the following three controls:

- 1 Control of water content—for improved concrete quality and economy.
- 2 Control of entrained air—for designed strength with required durability and low permeability.
- 3 Control of rate of hardening—for speed when needed, for retardation where required.

POZZOLITH and the LONDON-HILTON HOTEL

On the site of what will be London's most luxurious hotel—the London-Hilton—Ready Mixed Concrete Limited will deliver over 40,000 cubic yards of "Readymix" Concrete. Of this vast quantity, approximately 25,000 cubic yards is required for the foundations and floors. All this concrete contains **POZZOLITH**. Not only on this site, but on every project on which they've used the **POZZOLITH** method, Ready Mixed Concrete Limited have welcomed the advice of the **POZZOLITH** field men.

Why not call in the **POZZOLITH** field man for your next project.



POZZOLITH

Millars

For further details of **POZZOLITH** and the field and site service write to—

MILLARS' MACHINERY COMPANY LIMITED,
70 Pinner's Hall, Great Winchester Street, London, E.C.2.
Telephone: London W4 6206 (4 lines) 4286 1521 (3 lines)
Telegraphic Address: Millars, Stock, London.



**THE CHANGING SCENE
IN BRITAIN
OWES MUCH TO
TUNNEL CEMENT**

Tunnel Cement is playing a big part in today's building programmes, with a range that includes Masonry, White and Coloured Sulphate Resisting, Rapid Hardening and Waterproof Cements.

**The Tunnel Portland Cement
Company Limited,
185, Piccadilly, London, W.1.
Grosvenor 4104.**

TUNNEL CEMENT




FOR RELIABLE BAG AND BULK DELIVERIES

CYR-50

Patent Applications for Roofs.

Prestressed Roofs.

A PRESTRESSED concrete roof is formed by supporting reinforced concrete slabs 4 on cables or like tension members 3 suspended from and extending between supports 2, 7, 8 (*Fig. 1*), filling joints between slabs with mortar after all the slabs have been positioned, allowing the mortar to harden to produce a rigid roof unit, and then prestressing the concrete by tensioning the cables. The roof is assembled by laying the slabs at the lowest point and continuing uniformly on both sides, the slope at right angles to the cables being adjusted by suitable tensioning of cables 3.




In one embodiment, *Fig. 3*, the slabs 4 have reinforcing members 5 which project as hooks for engaging over the cables 3 which are enclosed in sheaths 9. The joints are filled with mortar 6; when this has set the cables are further tensioned to prestress the roof, and the cavities of sheathing tubes 9 are then filled with mortar under pressure. In another embodiment, *Fig. 7*, the slabs have projections or tongues 15 with grooves 16 for seating on cables 3 to which they are secured by bent reinforcing members 14. Hairpin loops 26 of reinforcement projecting from adjacent slabs are bound together by wires 12, and stirrups 10 are engaged around adjacent cables 3 and slab reinforcements 13. The slab ends at right angles to members 3 have quadrant shaped recesses filled with concrete and containing tensioning members.—No. 851,380. E. Lubbert, E. Schulz, U. Finsterwalder, R. Jecht, and E. Ruf. December 2, 1957.

Roof Trusses.

A JOINT between a lower end of an inclined reinforced or prestressed concrete

rafter 11, *Fig. 1*, a tie bar 13 and a support for the rafter wherein the point of intersection P of the line of thrust T of the support with the axis of the tie bar is located below the extended neutral axis of the central part of the rafter, and in which the resultant of the forces exerted on the rafter 11 by the tie bar 13 and support exerts on the rafter a bending moment in the direction tending to bow the rafter upwardly between its ends thereby effecting reduction of the bending moment at the centre of the rafter. The rafter 11 may be part of a truss which may include a second rafter 12 meeting the rafter 11 in a ridge joint 16, which may comprise a



resilient packing, and which is located below the intersection of the extended neutral axes of the central parts of the two rafters. The ridge joint also includes at least one tie bar 15 which may be secured by nuts and washers on its ends, *Fig. 5* (not shown). The invention may also be applied to a north-light truss, *Fig. 3*, in which additional reduction of bending moment is effected by an extension 25 on the shorter rafter 23, substantially in line with the longer rafter 23. The tie bars 13, 26 are supported by hangers 14, 27 respectively.—No. 861,676. G. Isaac. February 28, 1957.

Handbooks Received.

- "The Federation of Civil Engineering Contractors Handbook 1961-62." (London: 1961. Price 12s. 6d.)
- "Civil Engineering Films and Models." List of 111 films and fourteen models available from members of the Federation of Civil Engineering Contractors. Copies free from the Federation, Romney House, Tufton Street, London, S.W.1.

DATA FOR PRICING REINFORCED CONCRETE.**MATERIALS (Delivered London).****AGGREGATES (per cu. yd.).**Washed sand: 26s. 9d. Graded gravel ($\frac{3}{4}$ in.): 24s. 3d. Pit ballast: 23s. 6d.**CEMENT (per ton).**

Ordinary Portland.—8 tons and upwards: 115s. 3d.

Rapid-hardening Portland: As ordinary Portland plus 10s. 6d. "Aquacrete"

and "417": As ordinary Portland plus 32s. 6d. "Colorcrete" (buff, red,

and khaki): As ordinary Portland plus 60s. "Snowcrete" (white): 280s. 9d.

"Super-Cement": As ordinary Portland plus 32s. 6d.

High-alumina cement.—6 tons: 314s. 6d.

"Super Snowcem" waterproof cement paint: 100s. per cwt.

REINFORCEMENT (per ton ex stock including delivery in quantities from 10 to 500 tons).Plain mild steel rods per B.S. No. 785.—1 in. and over: £50 15s.; $\frac{7}{8}$ in. and $\frac{3}{4}$ in.:£51 10s.; $\frac{5}{8}$ in.: £52 5s.; $\frac{1}{2}$ in.: £53 18s.; $\frac{3}{8}$ in.: £55 8s. 6d.; $\frac{1}{4}$ in.: £59 9s. 6d.

Hot-rolled deformed bars: As plain bars plus £1.

High-tensile (minimum yield point 44,000 lb. per sq. in.): As mild steel plus 19s.

(For basic prices and allowances for quantities exceeding 500 tons and extras

for quantities less than 10 tons, lengths greater than 40 ft. or less than 5 ft., bundling, labelling, and delivery in other areas, see "Concrete Year Book, 1961".)

Fabric per B.S. 1221A (per sq. yd.).—No. 109: 3s. 7d.; No. 121: 5s. 7½d.; No. 124:

3s. 4½d.; No. 125: 2s. 10½d.; No. 126: 2s. 7d.

TIMBER.—Sawn deal shutter boards: £95 to £1.00 per standard (165 cu. ft.); 1-in.

boards: 1s. (av.) per sq. ft.; 1½-in. boards: 1s. 3½d. (av.) per sq. ft.

MATERIALS AND LABOUR.

Based on net cost of materials plus 10 per cent. and net cost of labour plus 50 per cent. for insurances, etc. (10 per cent.), on-costs (27 per cent.) and profit (10 per cent. on gross cost = 13½ per cent. on net cost). No allowance for non-productive ordinary time, overtime, travelling time, fares, subsistence, etc. Wages (per hour).—Carpenters and joiners: 5s. 7½d.; labourers: 5s.; mixer and hoist operators: 5s. 6d.; bar benders: 5s. 5½d.

PORTLAND CEMENT CONCRETE (1 : 2 : 4).

Foundations (per cu. ft.).—3s. 8d.

Suspended slabs (per sq. yd.).—6 in., 19s. 6d.; 7 in., 22s. 9d.; 9 in., 29s. 3d.

Beams (per cu. ft.).—4s. 4d. Columns (per cu. ft.).—4s. 11d.

Walls (per sq. yd.).—6 in., 21s. 5d.; 9 in., 32s. 1d.;

12 in. and over (per cu. ft.), 3s. 9d.

Extra (per cu. yd.) for rapid-hardening Portland cement, 1 : 2 : 4.—2s. 8d.

REINFORCEMENT.—Mild steel rods cut, bent and fixed (per cwt.).

	In floor slabs and beams.	In columns.	In walls.	Stirrups, binders, etc.
1 in. and over	78s. 1d.	84s. 7d.	82s. 0d.	—
$\frac{7}{8}$ in. and $\frac{3}{4}$ in.	78s. 10d.	85s. 4d.	82s. 9d.	—
$\frac{5}{8}$ in.	79s. 8d.	86s. 2d.	83s. 7d.	—
$\frac{1}{2}$ in.	88s. 0d.	95s. 10d.	93s. 3d.	—
$\frac{3}{8}$ in.	89s. 8d.	97s. 6d.	94s. 11d.	109s. 4d.
$\frac{1}{4}$ in.	91s. 11d.	99s. 9d.	97s. 2d.	111s. 7d.
$\frac{1}{8}$ in.	93s. 0d.	100s. 10d.	98s. 3d.	112s. 8d.

Fabric per B.S. No. 1221A in flat areas (per sq. yd.) including straight cutting.—

No. 109: 4s. 7d.; No. 121: 8s. 3d.; No. 124: 5s.; No. 125: 4s. 4½d.; No. 126: 3s. 9d.

SHUTTERING (FORMWORK).—Assuming five uses of wooden shutters for floor soffits and walls, and three uses for beams.

Soffits of floors, flat roofs, etc. (per sq. yd.): 17s. 8d.; ditto sloping: 19s. 1d.

Walls and partitions (per sq. yd.): 21s. 11d.; ditto curved: 29s. 9d.

Rectangular beams, lintels, columns, etc. (per sq. ft.): 2s. 11½d.; ditto circular: 4s. 2½d.

This page is prepared specially for "Concrete and Constructional Engineering" and is strictly copyright.



PRESTRESSING WIRES MAY LOOK ALIKE

BUT...

... Somerset wire is stabilized to give the lowest relaxation, both at normal and elevated temperatures. Somerset wire has stable elastic characteristics and zero residual elongation from normal working stresses. Maximum and proof stresses are guaranteed in accordance with B.S. 2691. There is a large ductility margin above working stress.

Somerset wire is available plain, indented or helically crimped, with degreased surface.

SOMERSET
STABILIZED
PRESTRESSING
WIRE

SOMERSET WIRE COMPANY LTD.
PENGAM MOORS
CARDIFF

Telephone: Cardiff 37485/6
Cables: Somwire, Cardiff



"CONCRETE SERIES"
BOOKS ON FOUNDATION ENGINEERING

AN INTRODUCTION TO DEEP FOUNDATIONS AND SHEET-PILING

By DONOVAN H. LEE, M.I.C.E., F.A.S.C.E., M.I.MECH.E.

This book is the successor to the author's "Sheet Piling, Cofferdams and Caissons". It is much enlarged and now deals with soil investigation, bearing piles, and sub-aqueous tunnels, as well as making and driving sheet-piles, the design of sheet-pile walls, and the design and construction of cofferdams, cylinders and open and pneumatic caissons. A feature is the numerous examples of actual works throughout the world.

Published September 1961

260 pages.

Price 20s.; by post 21s. 2d.

Numerous diagrams and photographs.
In Canada and U.S.A. 5 dollars.

DESIGN AND CONSTRUCTION OF FOUNDATIONS

By G. P. MANNING, M.ENG., M.I.C.E.

A dissertation, with much practical data, on the design of most ordinary foundations, including notes on constructional operations and materials. Many examples drawn from the Author's extensive experience. 226 pages. Numerous diagrams, working drawings, design charts etc.

Published July 1961

Price 24s.; by post 25s.

In Canada and U.S.A. 6 dollars.

FOUNDATION FAILURES

By C. SZECHY (Professor of Foundation Engineering, Budapest)

The author examines the causes of the failure, due to defective foundations, of numerous structures throughout the world and describes the remedial works undertaken.

Published March 1961

115 pages.

Price 20s.; by post 21s.

123 diagrams and photographs.
In Canada and U.S.A. 5 dollars.

REINFORCED CONCRETE PILING AND PILED STRUCTURES

By F. E. WENTWORTH-SHEILDS, W. S. GRAY, B.A., and H. W. EVANS.

Describes the design, manufacture, and driving of precast concrete piles. Design of piled structures with examples and illustrations. Design data in accordance with the latest British Codes of Practice.

Second Edition. Published 1960

149 pages, 116 illustrations, 17 tables.

Price 18s.; by post 19s.

In Canada and U.S.A. 4 dollars.

RAFT FOUNDATIONS.—THE SOIL-LINE METHOD

By A. L. L. BAKER, D.SC. (TECH.), A.M.I.C.E.

Describes in detail, with worked examples, the Soil-Line Method, a practical and economical way of taking into account variation of earth pressure.

Revised Edition. Published 1957

148 pages, 89 illustrations.

Price 12s.; by post 13s.

In Canada and U.S.A. 2-80 dollars.

For complete particulars of these and other books in the

"CONCRETE SERIES"

dealing with all aspects of design and construction in reinforced and prestressed concrete write to

CONCRETE PUBLICATIONS LTD.,
14 DARTMOUTH STREET, LONDON S.W.1

MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted, 5d. a word: minimum, 12s. Situations Vacant, 6d. a word: minimum, 15s. Other miscellaneous advertisements, 6d. a word: minimum, 15s. Displayed advertisements, 40s. per column inch. Box number 1s. extra.

Advertisements must reach this office, 14 Dartmouth Street, London, S.W.1, by the 26th of the month preceding publication.

SITUATIONS VACANT.

SITUATIONS VACANT. Experienced reinforced concrete designers and detailers required by structural engineers in their Westminster and Vauxhall offices. Pension scheme. Luncheon vouchers. Five-days' week, etc. Salary according to position and experience. Apply Box 4782, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Consulting engineers have vacancies for the following: Reinforced concrete designers with A.M.I.Struct.E.; Designer-detailers with H.N.C. or similar; Detailers with minimum two years' experience. The positions are permanent, with opportunity for advancement. Modern office and pleasant conditions. Salaries in accordance with experience. Apply BYLANDER, WADDELL & PARTNERS, 159 Wembley Park Drive, Wembley, or 10 Carver Street, Sheffield.

SITUATIONS VACANT. Designer-detailers with minimum of three years' experience in reinforced concrete required in our London and Guildford offices. Salary according to qualifications and experience. Pension scheme. Write or telephone for appointment, either Balham 2485 or Guildford 2483. TERNCO INDUSTRIAL DESIGN ENGINEERS, 11A Station Parade, Balham High Road, London, S.W.12.

SITUATIONS VACANT. Consulting civil and structural engineers require additional design staff in their London office. Qualifications: 3 to 6 years' experience. Degree or H.N.C. desirable but not essential. Five-days' week. Luncheon vouchers. Write MAURICE NACHSHEN & PARTNERS, 35 Victoria Street, London, S.W.1.

SENIOR TECHNICAL ASSISTANT
required for
RESEARCH DEPARTMENT
of
BRITISH RAILWAYS

British Railways have a vacancy for a Senior Technical Assistant in the Building Materials Laboratory located at Muswell Hill (alongside Alexandra Palace). Applicants must have at least a Higher National Certificate in Chemistry and a good chemical and practical knowledge of building materials and their uses.

The salary range for the post is £945-£1,145 per annum. Superannuation and travel facilities. Medical examination.

Applications, stating age, qualifications and experience, to

DIRECTOR OF RESEARCH (Dept. CC)
BRITISH RAILWAYS RESEARCH DEPT
222 MARYLEBONE ROAD
LONDON, N.W.1

by November 27.

SITUATION VACANT. Assistant engineer required for reinforced concrete design. Opportunity for young engineer to train for responsible position. Telephone Rickmansworth 2258.

SITUATIONS VACANT. OVE ARUP & PARTNERS require experienced reinforced concrete detailers. Applicants must have at least six years' experience of producing accurate working drawings. Apply in writing, giving details of previous experience, to 13 Fitzroy Street, London, W.1.

CONSULTING ENGINEERS

require immediately

several

ENGINEERING ASSISTANTS

for their


Sewerage, Sewage Purification and Structural Sections

Salaries between £650-£1,150, according to qualifications and experience. Contributory pension and bonus schemes in operation.

Applications, with relevant information including age, qualifications and experience, to

JOHN DOSSOR & ASSOCIATES

MONK BAR CHAMBERS
YORK

Join the 
team of

EXPERIENCED

**REINFORCED
CONCRETE
DESIGNER/DETAILERS
and DRAUGHTSMEN**

at any of the Design Offices at

STAFFORD	LEEDS
LONDON	LIVERPOOL
BIRMINGHAM	MANCHESTER
BRISTOL	NEWCASTLE
CHELMSFORD	GLASGOW
DUBLIN	

* Apply

Chief Engineer:

A. P. Mason, B.Sc., M.I.C.E., M.I. Struct. E., M.ASCE
THE BRITISH REINFORCED CONCRETE
ENGINEERING CO. LTD., STAFFORD

SITUATIONS VACANT. Experienced part-time assistants required by consulting engineers, Westminster, for design and/or detailing of reinforced concrete bridges and buildings. Write in confidence, stating age and full details of experience and qualifications, to Box 4771, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

STRUCTURAL ENGINEER EXCEPTIONAL OPPORTUNITY

Consulting Civil Engineers, Westminster, require a fully qualified structural engineer with wide experience for position of chief designer in reinforced and prestressed concrete for bridges and buildings. Knowledge of modern bridge design essential. Structural steelwork experience desirable.

Prospects of partnership interest in firm.

Write in confidence, stating age and full details of experience and qualifications, to Box 4766, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

FIRST-CLASS REINFORCED CONCRETE DETAILERS AND CIVIL ENGINEERING DRAUGHTSMEN

required by Consulting Engineers for wide range of work, including bridges. Excellent salaries and prospects. Permanent posts and pension scheme. Write, stating age and full details of experience, to

HARRY DROMPTON & PARTNERS,
7-8 Hobart Place,
Grovenor Gardens,
London, S.W.1.

SITUATIONS VACANT. Norris Consultants Limited have vacancies for senior civil/structural engineers with general design experience, particularly of industrial structures, power stations, multi-storey buildings and heavy foundations. Applications are invited from engineers aged 28-37 capable of controlling complete projects for one vacancy in London and three vacancies at Bristol Head Office. Permanent progressive appointments. Full details should be sent to NORRIS CONSULTANTS LTD., Beacon House, Queen's Road, Clifton, Bristol 8, with the reference Civil Project Engineers.

L.C.C. BRIXTON SCHOOL OF BUILDING

FERNDALE ROAD, LONDON, S.W.4

Required, as soon as possible, ASSISTANT GRADE B to teach CIVIL AND STRUCTURAL ENGINEERING SUBJECTS in sandwich and part-time courses. Applicants should be graduate in civil engineering and corporate member of appropriate professional institution. Teaching and/or industrial experience desirable.

Salary (at present under review) £750-£1,456, point of entry and maximum dependent on training, qualifications and experience.

Forms (foolscap s.a.e.) from Secretary, returnable within 14 days.

Please quote FE32/C/2930/11

SITUATION VACANT. Works Manager required for steel reinforcement specialists in Barking area. Able to take full charge of works and administration and have thorough knowledge of cutting, bending, control of labour, etc. Full details to Box 4785, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Harrow reinforced concrete engineers and contractors require experienced detailing-draughtsmen, also designers. Five-days' week, interesting work, modern offices, pension scheme after qualifying period. Write to BIEREUMS, 167/173 Imperial Drive, Harrow, or telephone for appointment FIELD End 7701.

EXPERIENCED

(United Kingdom born)

REINFORCED CONCRETE DESIGNERS AND DETAILERS REQUIRED

Numerous companies on our registers have vacancies for experienced men in these categories. We are specialists in such technical appointments. NO FEES.

BUSINESS VACANCIES BUREAU LTD.,
33 Victoria Street, London, S.W.1.
Telephone: ABBey 7390

NORRIS CONSULTANTS LTD

invite applications from

SENIOR, INTERMEDIATE and
JUNIOR ENGINEERS,

DESIGNERS and DRAUGHTSMEN
for vacancies in Bristol, London and Reading
in the following field

CIVIL AND STRUCTURAL ENGINEERING
AND BUILDING

Attractive and progressive salaries with insurance and pension schemes are available in an expanding organisation. Send personal details, quoting reference E.H.M., to our Head Office:

BEACON HOUSE · QUEEN'S ROAD
CLIFTON · BRISTOL 8

E. J. COOK & CO. (ENGINEERS) LTD.

invite

applications from

REINFORCED CONCRETE DESIGNERS AND DESIGNER/DETAILERS

who are at present earning £1,100 to £1,400 per annum, and are prepared to accept responsibility in a position offering interesting and varied experience in structural concrete design and an opportunity to gain experience in prestressed concrete and structural steelwork.

Write or telephone for application form from

54 SOUTH SIDE, CLAPHAM COMMON
LONDON, S.W.4
Telephone: MACaulay 5522

CIVIL ENGINEER

20 Albert Embankment, London, S.E.1.

THE SECRETARY,
JOHN LIVERSEDGE & ASSOCIATES,
42 PORTLAND PLACE, LONDON, W.1.

SITUATION WANTED. Qualified civil/structural engineer with exceptionally good experience in reinforced and prestressed concrete. All types of structures, bridges, power stations, and roads. Now available for position of responsibility. Box 4763, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

Telephone: METropolitan 8601 (10 lines)



Trent Gravels

Washed & Crushed $1\frac{1}{2}$ in. to $\frac{1}{2}$ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD

ATTENBOROUGH

NOTES

Telephone: Nottingham 25-4259

**CONCRETE
PROOFING
Co. LTD.**

**GUNITE
SPECIALISTS**

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request

116 Richmond Road, Kingston-upon-Thames, Surrey. Telephone: KINGSTON 7883 and 7152
And 10 Royal Crescent, Glasgow, C.3. Telephone: GLASGOW DOUGLAS 6371

SUBSCRIPTION RATES

The Proprietors of "Concrete and Constructional Engineering" regret to announce that, in view of the successive increases in the costs of printing and postage, the prepaid subscription rate for this journal will be 36s. per annum including postage (or 6.50 dollars in U.S.A. and Canada) as from January 1962.

The price of copies of current numbers, commencing with the number for January 1962, will be 3s. or by post 3s. 6d. (60 cents post paid in U.S.A. and Canada) each.

STONE COURT AGGREGATES




General View of Plant at Rickmansworth.

ONE OF OUR MODERN CONCRETE AGGREGATES PLANTS

First-Class Washed graded concrete aggregates, and shingles for road dressing, coupled with efficient delivery, are at the service of contractors and Municipal Authorities in London, Berks, Bucks, Herts, and Middlesex Areas.

Our products include Washed Sharp Sand, all sizes of shingles, from $3/16"$ up to $2"$, either crushed or natural.

Special Specifications made to order.



STONE COURT BALLAST CO. LTD.

FORTLAND HOUSE, TOTHILL ST., WESTMINSTER, S.W.1

Telephone: Tate Gallery 3456.



**CONCRETE
PROOFING
Co. LTD.**

**GUNITE
SPECIALISTS**

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request

116 Richmond Road, Kingston-upon-Thames, Surrey. Telephone: KINGSTON 7803 and 9152
And 10 Royal Crescent, Glasgow, C.3. Telephone: GLASGOW DOUGLAS 4371

SUBSCRIPTION RATES

The Proprietors of "Concrete and Constructional Engineering" regret to announce that, in view of the successive increases in the costs of printing and postage, the prepaid subscription rate for this journal will be 36s. per annum including postage (or 6.50 dollars in U.S.A. and Canada) as from January 1962.

The price of copies of current numbers, commencing with the number for January 1962, will be 3s. or by post 3s. 6d. (60 cents post paid in U.S.A. and Canada) each.

STONE COURT AGGREGATES



General View of Plant at Rickmansworth.

ONE OF OUR MODERN CONCRETE AGGREGATES PLANTS

First-Class Washed graded concrete aggregates, and shingles for road dressing, coupled with efficient delivery, are at the service of contractors and Municipal Authorities in London, Berks, Bucks, Herts, and Middlesex Areas.

Our products include Washed Sharp Sand, all sizes of shingles, from 3/16" up to 2", either crushed or natural.

Special Specifications made to order.



STONE COURT BALLAST CO. LTD.

PORTLAND HOUSE, TOTTILL ST., WESTMINSTER, S.W.1

Telephone: Tate Gallery 3456.






REINFORCED CONCRETE IS CONSTRUCTION AT ITS BEST

BRC FABRIC IS REINFORCEMENT AT ITS BEST

*Specialists in Reinforced Concrete Design
and Suppliers of Reinforcement*

THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD

London, Birmingham, Bristol, Chelmsford, Leeds, Leicester, Liverpool, Manchester, Newcastle, Cardiff,
Glasgow, Dublin, Belfast, Bulawayo, Calcutta, Johannesburg, Singapore, Vancouver
Export Sales: 54 Grosvenor Street, London W.1

64-17, 1918

Published by CONCRETE PUBLICATIONS LTD., 14 Dartmouth Street, London, S.W.1. Telephone: Whitehall 4581
Printed by BUTLER & TANNER LTD., The Solwood Printing Works, Frome and London

